# **TECHNICAL FISHERY REPORT 88-13**



Alaska Department of Fish and Game Division of Commercial Fisheries PO Box 3-2000 Juneau, Alaska 99802

October 1988

Stock Compositions of Sockeye Salmon Catches in Southeast Alaska's Districts 106 and 108 and in the Stikine River, 1987, Estimated with Scale Pattern Analysis

by
Kathleen A. Jensen
and
Iris S. Frank

State of Alaska

Steve Cowper, Governor

The Technical Fishery Report Series was established in 1987, replacing the Technical Data Report Series. The scope of this new series has been broadened to include reports that may contain data analysis, although data oriented reports lacking substantial analysis will continue to be included. The new series maintains an emphasis on timely reporting of recently gathered information, and this may sometimes require use of data subject to minor future adjustments. Reports published in this series are generally interim, annual, or iterative rather than final reports summarizing a completed study or project. They are technically oriented and intended for use primarily by fishery professionals and technically oriented fishing industry representatives. Publications in this series have received several editorial reviews and at least one blind peer review refereed by the division's editor and have been determined to be consistent with the division's publication policies and standards.

# STOCK COMPOSITIONS OF SOCKEYE SALMON CATCHES IN SOUTHEAST ALASKA'S DISTRICTS 106 AND 108 AND IN THE STIKINE RIVER, 1987, ESTIMATED WITH SCALE PATTERN ANALYSIS

Ву

Kathleen A. Jensen

and

Iris S. Frank

Technical Fishery Report No. 88-13

Alaska Department of Fish and Game Division of Commercial Fisheries Juneau, Alaska

October 1988

#### **AUTHORS**

Kathleen A. Jensen is a Region I Fishery Biologist for the Alaska Department of Fish and Game, Division of Commecial Fisheries, P.O. Box 20, Douglas, AK 99824.

Iris S. Frank is a Region I Fishery Technician for the Alaska Department of Fish and Game, Division of Commercial Fisheries, P.O Box 20, Douglas, AK 99824.

#### **ACKNOWLEDGEMENTS**

We are grateful to personnel of the Port Sampling Project of the Division of Commercial Fisheries, Southeast Region, Alaska Department of Fish and Game and to personnel of the Canadian Department of Fisheries and Oceans for their assistance in gathering samples from catches and escapements. In particular, we would like to thank Ben Van Alen, Keith Pahlke, Cathy Robinson, Nancy Rattner, and Karl Hofmeister of ADF&G Commercial Fisheries and Sandy Johnson and Peter Etherton of CDFO for their smooth coordination of sampling efforts. We gratefully acknowledge the efforts of Craig Farrington for aging scales, of Scott McPherson for scale aging consultations, and of Dr. Norma Jean Sands for biometric review.

#### PROJECT SPONSORSHIP

This investigation was partially financed with Anadromous Fish Conservation Act (P.L. 89-304 as amended) funds under Project No. AFC-72 and with U.S./Canada Pacific Salmon Treaty funds under Cooperative Agreement NA-87-ABH-00025.

# TABLE OF CONTENTS

<u>Page</u>
LIST OF TABLES
LIST OF FIGURES
LIST OF APPENDICES
ABSTRACT
INTRODUCTION
Objectives
Study Area
Stock Separation Studies
MATERIALS AND METHODS
Collection and Preparation of Scale Samples
Age Determination and Measurement of the Scales 4
Analytical Procedures
Developing Standards
Classification of Catches 6
Estimation of the Stikine River Sockeye Run
Comparison of In- and Postseason Estimates 9
RESULTS
Stock Composition of the Subdistrict 106-30 Catch
Stock Composition of the Subdistrict 106-41 Catch
Stock Composition of the District 108 Catch
Stock Compositions of the Stikine River Catches
Stikine River Run Strength
Comparison of In- and Postseason Analyses
DISCUSSION
LITERATURE CITED
APPENDICES

# LIST OF TABLES

<u>Table</u>	<u> </u>	<u>age</u>
1.	Log-likelihood (G) values for a comparison of estimates in Alaska's District 108 commercial and test drift gill net fisheries, 1985-1987	21
2.	Estimated contributions of sockeye salmon stock groups to Alaska's District 106 and 108 commercial drift gill net fisheries, 1987	22
3.	Estimated contributions of Tahltan and non-Tahltan sockeye salmon stock groups to the Stikine River test fishery and to Canada's lower river commercial fishery, 1987	23
4.	Mean classification accuracies from linear discriminant function models used to classify sockeye salmon harvested in Alaska's Districts 106 and 108 and Canada's Stikine River gill net fisheries, 1987	24
5.	Catch and escapement of Stikine River sockeye salmon, 1987	25
6.	Log-likelihood (G) values for the comparison of weekly inseason and postseason stock composition estimates for sockeye salmon harvested in Alaska's District 106 and Canada's Stikine River commercial gill net fisheries, 1987	26

# LIST OF FIGURES

<u>Figure</u>		Page
1.	Southeast Alaska, northern British Columbia, and the transboundary Stikine River	27
2.	Major sockeye salmon systems of Southeast Alaska. Numbers identify lakes where scale samples have been collected and x indicates systems where scales were collected in 1987	28
3.	The transboundary Stikine River, major tributaries, and fishery areas	29
4.	Typical scale for age-2. and -1. sockeye salmon with zones used for scale pattern analysis delineated	30
5.	Weekly harvest of major sockeye salmon stock groups in Alaska's Subdistrict 106-30 drift gill net fishery, 1987	31
6.	Proportion of each major sockeye salmon stock group in the weekly catch in Alaska's Subdistrict 106-30 drift gill net fishery, 1987	32
7.	Migratory timing of major sockeye salmon stock groups as indicated by the weekly proportion of a total stock group CPUE in Alaska's Subdistrict 106-30 drift gill net fishery, 1987	33
8.	Weekly harvest of major sockeye salmon stock groups in Alaska's Subdistrict 106-41 drift gill net fishery, 1987	34
9.	Proportion of each major sockeye salmon stock group in the weekly catch in Alaska Subdistrict 106-41 drift gill net fishery, 1987	35
10.	Migratory timing of major sockeye salmon stock groups as indicated by the weekly proportion of a total stock group CPUE in Alaska's Subdistrict 106-41 drift gill net fishery, 1987	36
11.	Weekly harvest of Tahltan and Stikine sockeye salmon and relative abundance of the two stock groups in Canada's lower Stikine River commercial fishery, 1987	37
12.	Weekly catch of Tahltan and Stikine sockeye salmon and relative abundance of the two stock groups in the Stikine River test fishery, 1987	38
13.	Migratory timing of the Tahltan and Stikine sockeye stock groups as indicated by the weekly proportion of total stock group CPUE in the Stikine River test fishery, 1987	39

## LIST OF APPENDICES

		<u>Page</u>
APPENDIX A:	SAMPLE SIZES AND SCALE VARIABLES	
A.1 -	Sample sizes from the in-season sockeye salmon stock composition estimates from Alaska's Districts 106 and 108 and Canada's Stikine River commercial gill net fisheries, 1987	41
A.2 -	Sample sizes from the postseason sockeye salmon stock composition estimates from Alaska's Districts 106 and 108 and Canada's Stikine River gill net fisheries, 1987	42
A.3 -	Scale variables used for the age-1.2, -1.3, -2.2, and -2.3 sockeye salmon scale pattern analysis	43
APPENDIX B:	CLASSIFICATION MATRICES	
B.1 -	Classification matrices for linear discriminant function models used to classify age-1.2 sockeye salmon from Alaska's Districts 106 and 108 and Canada's Stikine River gill net fisheries, 1987	46
B.2 -	Classification matrices for linear discriminant function models used to classify age-1.3 sockeye salmon from Alaska's Districts 106 and 108 and Canada's Stikine River gill net fisheries, 1987	47
B.3 -	Classification matrices for linear discriminant function models used to classify age-2.2 sockeye salmon from Alaska's Districts 106 and 108 and Canada's Stikine River gill net fisheries, 1987	49
B.4 -	Classification matrices for linear discriminant function models used to classify age-2.3 sockeye salmon from Alaska's Districts 106 and 108 and Canada's Stikine River gill net fisheries, 1987	50
APPENDIX C:	DISTRICT 106 AND 108 STOCK COMPOSITIONS	
C.1 -	Estimated contributions of sockeye salmon stocks originating in Alaska and Canada to Alaska's Subdistrict 106-30 drift gill net fishery, 1987	51
C.2 -	Estimated CPUE and migratory timing of sockeye salmon stocks in Alaska's Subdistrict 106-30 drift gill net fishery, 1987	52

# LIST OF APPENDICES (Continued)

				<u>Page</u>
ı	C.3	-	Estimated contributions of sockeye salmon stocks originating in Alaska and Canada to Alaska's Subdistrict 106-41 drift gill net fishery, 1987	53
l	C.4	-	Estimated CPUE and migratory timing of sockeye salmon stocks in Alaska's Subdistrict 106-41 drift gill net fishery, 1987	54
	C.5	-	Estimated contribution of sockeye salmon stocks originating in Alaska and Canada to Alaska's District 108 drift gill net fishery, 1987	55
APP	ENDIX	( D:	HISTORICAL STOCK COMPOSITIONS IN DISTRICTS 106 AND 108	
	D.1	-	Estimated contributions of sockeye salmon stock groups to Alaska's District 106 drift gill net fisheries (1982-1987)	
	D.2	-	Estimated contribution rates of sockeye salmon stock groups to Alaska's District 106 drift gill net fisheries (1982-1987)	57
	D.3	-	Estimated contributions of sockeye salmon groups to Alaska's Subdistricts 106-30 and 106-41 drift gill net fisheries (1985-1987)	58
	D.4	-	Estimated contribution rates of sockeye salmon stock groups to Alaska's Subdistricts 106-30 and 106-41 drift gill net fisheries (1985-1987)	59
	D.5	-	Estimated contributions of sockeye salmon stock groups to Alaska's District 108 drift gill net fisheries 1986-1987	60
	D.6	-	Estimated contributions of sockeye salmon stock groups to Alaska's District 108 drift gill net test fisheries, 1985-1986	61
APP	ENDI	Κ E:	STOCK COMPOSITIONS OF THE STIKINE RIVER FISHERIES	
	E.1	-	Estimated contribution of sockeye salmon stocks of Tahltan and non-Tahltan origin to Canada's Stikine inriver commercial fishery, 1987	62
	E.2	-	Estimated CPUE and migratory timing of the Tahltan and non-Tahltan sockeye salmon stock groups in Canada's Stikine River commercial fishery, 1987	63

# LIST OF APPENDICES (Continued)

		Page
E.3 -	Estimated contribution of sockeye salmon stocks of Tahltan and non-Tahltan origin to the Stikine River test fishery, 1987	64
E.4 -	Relative run strength and migratory timing of the Tahltan and non-Tahltan sockeye salmon in the Stikine River test fishery, 1987	65
APPENDIX F:	COMPARISON ON IN- AND POSTSEASON STOCK COMPOSITION ESTIMATION	ΓES
F.1 -	In-season initial and adjusted stock composition estimates for sockeye salmon harvested in Alaska's Subdistrict 106-30 drift gill net fishery, 1987	66
F.2 -	Postseason initial and adjusted stock composition estimates for sockeye salmon harvested in Alaska's Subdistrict 106-30 drift gill net fishery, 1987	67
F.3 -	Differences between in- and postseason stock composition estimates for Alaska's Subdistrict 106-30 sockeye harvest, 1987	68
F.4 -	Log-likelihood (G) values for a comparison of weekly in-season and postseason stock composition estimates for Alaska's Subdistrict 106-30 drift gill net sockeye harvest, 1987	69
F.5 -	In-season initial and adjusted stock composition estimates for sockeye salmon harvested in Alaska's Subdistrict 106-41 drift gill net fishery, 1987	70
F.6 -	Postseason initial and adjusted stock composition estimates for sockeye salmon harvested in Alaska's Subdistrict 106-41 drift gill net fishery, 1987	71
F.7 -	Differences between in- and postseason stock composition estimates for Alaska's Subdistrict 106-41 sockeye harvest, 1987	72
F.8 -	Log-likelihood (G) values for a comparison of weekly in-season and postseason stock composition estimates for Alaska's Subdistrict 106-41 drift gill net sockeye harvest, 1987	73
F.9 -	In-season initial and adjusted stock composition estimates for sockeye salmon harvested in Canada's Stikine River commercial fishery, 1987	74

# LIST OF APPENDICES (Continued)

		<u>Page</u>
F.10 -	Postseason initial and adjusted stock composition estimates for sockeye salmon caught in the Stikine River test fishery and in Canada's lower river commercial fishery, 1987	75
F.11 -	Differences between the in- and postseason stock composition estimates for Canada's Stikine River sockeye harvest, 1987	76
F.12 -	Log-likelihood (G) values for a comparison of weekly in- and postseason stock composition estimates for Canada's Stikine River commercial sockeye harvest, 1987	77
		• • •

#### **ABSTRACT**

Linear discriminant function analysis of scale patterns was used to estimate the 1987 sockeye salmon (Onchorynchus nerka) stock compositions in the commercial gill net fisheries in Southeast Alaska's Districts 106 and 108, in the Stikine River test fishery, and in the Canadian lower river commercial fishery. Contributions of the Alaska I, Alaska II, Canadian Nass/Skeena, and transboundary Stikine River stock groups to Alaska's District 106 and 108 fisheries were estimated to be 66,541, 46,043, 21,190, and 3,655 sockeye salmon, respectively. The commercial fishery stock specific weekly CPUE is an indicator of migratory timing. The CPUE in District 106 was greatest July for the Alaska I stock group, during late July through early August for the Alaska II group, and during early August for the Nass/Skeena group. Weekly catches of the Tahltan and non-Tahltan Stikine River stocks were too small to be used to estimate migratory Canada's Stikine River commercial and food fishery catches were estimated to be 4,509 Tahltan and 5,106 non-Tahltan Stikine fish, while estimated escapements were 6,958 Tahltan and 17,055 non-Tahltan Stikine fish. The 1987 Stikine River sockeye run was estimated to be 33,628 fish. An additional 603 Tahltan and 1,355 non-Tahltan Stikine sockeye salmon were caught in district and inriver test fisheries. Tahltan stocks contributed more than 65% of the weekly Canadian commercial catch through July 18, while the non-Tahltan Stikine stocks contributed more than 75% of the weekly catch after July 19. In-season estimates of stock proportions, used to provide guidelines for managers in making fishery extension or closure decisions were not significantly different from post season estimates during most weeks.

**KEY WORDS:** 

sockeye salmon, linear discriminant function, scale pattern analysis, stock composition, transboundary, migratory timing, in-season analysis, Stikine sockeye, Tahltan, non-Tahltan Stikine, *Oncorhynchus nerka* 

#### INTRODUCTION

Sockeye salmon (Oncorhynchus nerka) are harvested in marine net fisheries throughout Southeast Alaska and northern British Columbia. Drift gill net fisheries in Alaska's commercial fishing Districts 106 and 108 harvest sockeye salmon of Alaskan origin, but also catch some sockeye salmon of transboundary Stikine River origin and some fish destined to spawn in the Nass and Skeena Rivers of Canada. Interception of salmon bound for one country's rivers as they migrate through the territorial waters of the other country has become a research and management concern in recent years with the implementation of the U.S./Canada Pacific Salmon Treaty. Cooperative international management of Stikine River sockeye salmon is mandated by this treaty under Annex IV, Chapter 1. Knowledge and control of stock-specific harvest is, therefore, needed to fulfill requirements of and assess compliance with the harvest sharing guidelines outlined in the treaty.

#### Objectives

The purpose of this study is to determine the contributions of major sockeye stock groups to: (1) gill net fisheries in Alaska's Subdistricts 106-41 and 106-30 and District 108, (2) Canada's commercial fisheries in the Stikine River, and (3) the Stikine River test fishery. This study provides in-season information on the abundances of local sockeye stocks that is used by managers in making harvest level decisions. Postseasonally it provides revised estimates of stock composition which are used to finalize estimates of stock compositions. An estimate of the total Stikine River sockeye run is derived from data analyzed in this study. Estimation of the interception rates and relative abundance of Stikine River sockeye salmon is of major importance in helping managers from the Alaska Department of Fish and Game (ADF&G) and the Canadian Department of Fisheries and Oceans (CDFO) implement treaty guidelines.

#### Study Area

Sockeye salmon harvested in the Districts 106 and 108 commercial fisheries originate from lake systems and their tributaries throughout Southeast Alaska, from the sloughs and lakes of the transboundary Stikine River, and from the Canadian Nass and Skeena Rivers (Figure 1). Tagging studies have shown that few stocks from other than the above areas pass through District 106 (Steve Hoffman, Alaska Department of Fish and Game, personal communication). In the above studies adult sockeye salmon were tagged in 1982 and 1983 in several Alaskan and Canadian fishing districts to determine migratory pathways and interception rates of various stocks. The majority of terminal area recoveries from fish tagged in District 106 occured along the northeast coast of Prince of Wales Island and upper Behm Canal. Tags applied in this district were also recovered in Alaskan systems as far south as the U.S./Canada border, and in the Stikine, Nass, and Skeena Rivers. There were few or no recoveries of tags applied in more

southern districts in either the northern Prince of Wales Island lake systems or the Stikine River.

Numerous sockeye salmon producing lakes are scattered throughout the achipelago and mainland of Southeast Alaska. They range in size from small lakes of a few hectares to large systems greater than 500 hectares (e.g., McDonald and Klawock Lakes) and include multi-lake systems like the Sarkar and Galea-Sweetwater complexes (Figure 2). Sockeye salmon production is limited by the quantity and quality of spawning areas, the available rearing area, or other environmental conditions as well as the number of spawners. Sockeye productivity varies greatly, even among systems of roughly equivalent size (McGregor 1983; McGregor et al. 1984; McGregor and McPherson 1985; McPherson and McGregor 1986; and McPherson et al. 1988a, 1988b). Typical small systems, such as Alecks and Kutlaku Lakes on Kuiu Island, produce estimated runs of a few thousand fish. While total run size is not known escapements in two intermediate systems, which had enumeration weirs, Karta Lake on eastern Prince of Wales Island and Salmon Bay Lake on northeast Prince of Wales Island averaged 21,500 and 15,300 sockeye salmon (1982 to 1987, excluding 1984 for Karta when a weir was not installed). The single largest producer of sockeye salmon in recent years in southern Southeast Alaska has been McDonald Lake, located in upper Behm Canal. Escapements to this system have ranged from 56,000 in 1983 to 175,000 in 1987 and averaged 119,000 (1981 to 1987, excluding 1982 when the weir washed out).

The Stikine River is a transboundary river that originates in British Columbia, crosses the Alaskan panhandle, and flows into Frederick Sound north of Wrangell. Approximately 90% of the river system is inaccessible to anadromous fish due to natural barriers and velocity blocks. The majority of the accessible sockeye spawning habitat is located above the U.S./Canada border. The largest single contributor to the Stikine River sockeye run is the Tahltan Lake group, hereafter referred to as Tahltan. This system has a weir and sockeye escapement counts have ranged from 1,800 fish in 1963 to 67,300 fish in 1985 and averaged 20,600 (1959 to 1987, excluding 1962 when the weir installation date was unspecified and 1965 when a large slide hindered access into the lake) (TTC 1987). The remainder of the Stikine River sockeye stocks (the non-Tahltan Stikine stock group), spawn in small sloughs, and side channels of the mainstem river tributaries, most of which are glacially occluded. Non-Tahltan Stikine sockeye escapement estimates have ranged from 13,400 in 1979 to 63,000 in 1985 and averaged 32,200 (1979 to 1987). A Canadian subsistence fishery operating near Telegraph Creek has harvested a yearly average of 3,525 fish (1972 to 1987) (CDFO 1986; Sandy Johnson, CDFO, personal communication). Canadian commercial fisheries on the upper and lower portions of the river have harvested an average of 832 and 14,638 sockeye salmon, respectively (1979 to 1987, excluding 1984 when both were closed).

The Nass and Skeena Rivers also contribute substantial numbers of sockeye salmon to the District 106 and 108 harvests in some years. The Nass River originates in British Columbia and drains into Portland Canal, just south of the U.S./Canada border. Estimated sockeye escapements to this system have averaged 227,400 from 1980 to 1987. The Skeena River also originates in British Columbia and drains into the ocean about 50 km south of the Nass

River. Estimated sockeye escapements have averaged 1,158,800 from 1980 to 1986 (TTC 1988; Barbara Snyder, CDFO, personal communication).

#### Stock Separation Studies

The United States and Canada inititated research programs in 1982 to assess the feasibility of various stock separation techniques applicable to sockeye salmon stocks harvested by both countries. Several methods of stock separation have been used, including: the incidence of the parasite Myxobolus neurobius, differences in genotypes, adult tagging studies, and scale pattern analysis. Of these, scale pattern analysis has been used most extensively to determine stock composition of the harvests in Alaskan mixed stock commercial fisheries (Oliver et al. 1984; Oliver and Walls 1985; Oliver and Jensen 1986; Jensen et al. 1988).

Scale pattern analysis has proven highly successful in determining the contribution rates of sockeye stocks to Southeast Alaska's commercial fisheries because of significant and persistent differences in the freshwater and early marine growth among stocks originating in various Alaskan and Canadian systems. The original stock groupings used by ADF&G were the Alaska group (comprised of samples taken from 22 to 28 Alaska escapements), Nass/Skeena group (comprised of samples taken from inriver test fisheries on the Nass and Skeena Rivers), and Stikine River group (comprised of scale samples collected from the Canadian inriver commercial fishery). The stock groupings were expanded in 1983 by creating separate standards for the Tahltan Lake escapement and for the non-Tahltan Stikine escapement (samples from mainstem river and side slough spawners and Chutine, Skud, and Iskut River spawners). Standards were further refined in 1986 to separate two distinct Alaska patterns (Alaska I, typified by Salmon Bay and Hugh Smith Lake patterns and Alaska II, typified by the McDonald Lake pattern). The 1987 standards were created in the same manner as in 1986.

#### MATERIALS AND METHODS

#### Collection and Preparation of Scale Samples

One to three scales were taken from each of 700 sockeye salmon randomly sampled from the commercial catches in Alaska's Subdistricts 106-41 and 106-30 during each week the fisheries were open and in District 108 from one week (mid-July, week 29) only (McPherson et al. 1988b). Scale samples from the Stikine River test fishery and from the Canadian commercial catch were collected by ADF&G and CDFO personnel. Stock group standards used in postseason analysis were developed from scales sampled from 1987 escapements. Approximately 500 scales were collected from each of 16 lake systems throughout Southeast Alaska (Figure 2), 1000 scales at the Tahltan weir (Figure 3), 200 from non-Tahltan Stikine escapements, and approximately 1000 to 1500 from each test fishery operating in the lower reaches of the Nass and Skeena Rivers (Figure 1). The standards used in the

in-season analysis were developed from scales collected in the same areas in 1986.

Scales were taken from the left side of each fish approximately two rows above the lateral line in the area transected by a diagonal line between the posterior insertion of the dorsal fin to the anterior insertion of the anal fin (INPFC 1963). Scales of salmon fry develop first in this area, and thus, for purposes of aging and digitizing, it is the prefered area. Scales were mounted on gum cards and impressions made in cellulose acetate (Clutter and Whitesel 1956).

#### Age Determination and Measurement of the Scales

A sampling goal of scales from 700 fish per district per week was established for the age composition estimation. Individual fish ages were determined from scale images magnified 70X on a microfiche reader and were recorded in European notation. The sample size used for the scale pattern analysis varied on a weekly basis and was dependent on age composition. Generally scales from 100 age-1.3 fish and as many scales as possible (up to 100) from each of the age-1.2, -2.2, and -2.3 groups were analyzed for each district or subdistrict and week (Appendix A.1 and A.2). Scale images magnified at 100X were projected onto a digitizing tablet using equipment similar to that described by Ryan and Christie (1976). Scale measurements were made and recorded with a microcomputer-controlled digitizing system with fortran programs.

Previous studies have established that an axis approximately perpendicular to the anterior edge of the unsculptured posterior field is best for consistently measuring sockeye scales (Clutter and Whitesel 1956; Narver 1963). This axis is approximately 20° dorsal or ventral from the anteriorposterior axis, and all circuli counts and scale measurements in the lacustrine and first year marine zone were made along it. Marshall et al. (1984) established the separability of major stock groups by measurements in three (or four) zones: (1) the scale center to the last circulus of the first freshwater annulus, (2) when present, the first circuli of the second year of freshwater growth to the end of the second freshwater annulus, (3) the plus growth or scale growth after the last freshwater annulus and before the first marine circulus (Mosher 1968), and (4) the first year marine growth (i.e., the first marine circulus to the end of the first marine annulus) (Figure 4). A total of 74 variables, including circuli counts, incremental distances, and ratios and/or combinations of the measured variables are calculated for samples with a single freshwater annular zone and 106 variables for samples with two freshwater annular zones (Appendix A.3).

#### Analytical Procedures

The ability to differentiate salmon stocks based on scale patterns depends upon the degree of difference in the scale characters among stocks (Marshall et al. 1987). Linear discriminant function (LDF) analysis of

scale patterns has been used to estimate stock contribution to southern Southeast Alaska mixed stock sockeye salmon fisheries since 1982 (Oliver et al. 1984; Oliver and Walls 1985; Oliver and Jensen 1986; Jensen et al. 1988).

LDF is a multivariate technique that is used to develop classification rules used to assign a sockeye salmon sampled in a mixed stock fishery to a stock of origin. The variables calculated from the circuli counts and incremental distances on scales from fish of known origin provide a set of measurements used to define these rules. A sample of p selected scale variables from a number of salmon stocks or stock groups defines a single region in p-space characteristic of that group of fish. Based on probability theory, the established regions in p-space are uniquely defined or separated by decision surfaces. A sockeye salmon harvested in a mixed stock fishery may be classified according to which region its p-tuple occupies. The accuracy of classification depends upon the precision with which the regions defining each stock or group are described and the inherent separation between them. The LDF is the linear combination of p observed variables which maximizes the between-group variance relative to the within-group variance (Fisher 1936).

The major assumptions underlying LDF analysis are: (1) the groups being investigated are discrete and identifiable; (2) the parent distributions of the measured variables are multivariate normal; and (3) the variance-covariance matrices for all groups are equal. Gilbert (1969) found LDF satisfactory if the variance-covariance matrices were not too different from each other. Large sample sizes appear to make the LDF robust to the assumption of common variance-covariance matrices (Issacson 1954; Anas and Murai 1969). The method also appears to be robust to violations of the normality assumption for discrete distributions, however, it is not robust for continuous non-Gaussian parent distributions (Lachenbruch et al. 1973; Krzanowski 1977).

The 2 to 10 scale variables to be used in the LDF are selected from among 106 variables using a stepwise regression procedure (Enslein et al. 1977). In this process variables are added until the partial F-statistic of each variable not yet entered into the model is less than 4.00. An almost unbiased estimate of classification accuracy for each LDF was determined using a leaving-one-out procedure (Lachenbruch 1967). One sample is "left-out", the discriminant rule is estimated, and the "left-out" sample is classified using the discriminant rule and checked to see if it was classified correctly. This procedure is repeated for all samples. Thus, when an LDF is run using the leaving-one-out procedure, a classification matrix is developed which gives the proportion of correctly identified fish and the proportion of misclasification of each stock to each of the other stocks.

When more than two stock groups are being analyzed, the stepwise regression procedure does not always result in maximum classification accuracies or the most balanced classification matrix. Frequently, well-separated groups are separated even further, while poorly separated groups remain poorly separated (Habbema and Hermans 1977). Scale variables that provided the best discrimination between the groups (high F value) that most often misclassified as each other were occasionally added to or substituted for

other variables used in the LDF to provide either a better balance to the classification matrix, or to increase the mean classification accuracy.

The estimates of stock composition proportions in the mixed stock harvests, referred to as initial estimates, were adjusted with a classification matrix correction procedure (Cook and Lord 1978). The fish in the mixed stock composition sample are classified with the LDF. The vector of estimates for each stock or stock group is multiplied by the classification matrix to give new estimates, referred to as adjusted estimates, for the true proportions of stocks and stock groups in the mixed stock fishery. In cases where adjusted estimated proportions for a stock group were less than zero, the entire catch sample was reclassified with a model excluding that stock group. This process was repeated until all adjusted estimated proportions were positive.

The variance and 90% confidence intervals of the adjusted estimates of stock proportions were computed according to Pella and Robertson (1979). The variance-covariance matrices for the misclassification matrix and for the mixed stock proportion vector are determined from the multinomial probability distribution. These two variance-covariance matrices are combined to give variances and covariances for the adjusted estimates of stock proportions. The variances for the proportions of each stock are the diagonal elements of this combined matrix, i.e., they are an additive combination of: (1) the sampling variation in estimation of the probability of assignment of the known stock group, and (2) the sampling variation in estimation of the assignment composition of the mixed stock group.

## Developing Standards

The four major age groups (1.2, 1.3, 2.2, and 2.3) have generally contributed more than 98% of the catch in Districts 106 and 108. Standards were developed for each age class for the Alaska I and Nass/Skeena groups and for age-1.2, -1.3, and -2.3 fish for the Alaska II group. Tahltan standards were developed for age-1.3 and -2.3 fish and non-Tahltan Stikine standards were developed for the age-1.3 fish only. Standards were not developed for age classes which contributed only a minor fraction of the escapement for a given stock or stock group since insufficient scales were available to build them. Age-specific models, where standards from age-1.3 fish were used to classify catches of age-1.3 fish, were used in the analysis to: (1) account for differences in age composition among stocks, (2) remove potential bias due to differences in migratory timing of different age fish, and (3) eliminate the effect of different environmental conditions on the scale patterns of different age fish.

#### Classification of Catches

Commercial catches were analyzed in-season with standards developed from the previous year's escapements. Stock contributions for the Subdistrict 106-41 and 106-30 and for one week of the District 108 commercial harvests were estimated and summaries provided to managers within 48 h of the

fishery closures from mid-June through early August. Three of the four major age groups (1.2, 1.3, and 2.3) were analyzed; the fourth, age-2.2, comprized primarily of the Alaska I and Nass/Skeena stocks was not digitized in-season due to time constraints. Stock compositions for the Canadian commercial catches on the Stikine River were also estimated inseason, however, there was a 3- to 5-d lag between fishery closures and catch analyses due to logistical difficulties in receiving the data. The commercial catches were reclassified postseasonally with standards built from the 1987 escapements. Commercial catches which had occured after the cessation of the in-season analysis and catches from the Stikine River test fishery were also classified postseasonally.

Stock contributions were estimated for each week to track temporal patterns; however, in some weeks catches were small and samples of the less common age groups were insufficient to classify, unless pooled with the adjacent week's sample. The proportion of each stock in a week's catch sample was expanded to the week's catch by:

$$C_{i,jt} = C_t * P_{it} * S_{i,jt}$$
 (1)

where:  $C_{ijt}$  = estimated catch of fish of age i and group j in time period

Ct = total catch in time period t,

P<sub>it</sub> = estimated proportion of fish of age i in the catch in time period t, and

 $S_{ijt}$  = proportion of fish of age i and group j in the catch in time period t estimated with LDF.

The stock apportionment of the minor age groups not classified with LDF assumes that the proportion of the minor ages belonging to any given stock is equal to the combined proportion of all LDF classified age classes:

$$C_{mjt} = C_t * P_{mt} * S_{jt}$$
 (2)

where:  $C_{mjt}$  = estimated catch of fish of minor age classes of group j in time period t and

 $P_{mt}$  = estimated proportion of fish of minor age groups in the catch in time period t.

S. jt = proportion of fish in all age classes in group j in the catch in time period t estimated with LDF.

Sockeye catches in Alaska's District 108 were sampled during mid-July only (statistical week 29). The contributions of Stikine River stocks in each unsampled week in 1987 were estimated by averaging the contributions of Stikine River stocks during the same week during prior years based on

hypothesis test of no significant difference between years (Table 1). No variances were calculated for stock compositions estimated in this manner.

The variances (V) of the weekly (C. $_{it}$ ) and seasonal (C. $_{j.}$ ) stock composition estimates were approximated with the delta method (Seber 1982). The variance estimates are functions of: (1) The accuracy of the agespecific models used to classify the unknowns, (2) the sample size of each standard used to develop the age-specific models, (3) the proportions of each stock in the initial and in the adjusted stock composition estimates, (4) the age-specific stock composition sample sizes, (5) the age composition sample sizes, and (6) the catch size. However, it is a minimum estimate of variance since it does not include any variance associated with the age classes not classified with LDF, any variance for stocks contributing no fish during a given week, nor any estimator of aging errors.

Variances of the proportions of stock contributions were calculated by

$$V(P_j) = P_j^2 \times (\frac{V(C_j)}{C_j^2} + \frac{V(C_s)}{C_s^2})$$
 (3)

where:  $P_j$  = Proportion of stock j or  $C_j/C$ .

The postseason classifications of the Stikine River commercial and test fishery catches were run with 2-way Tahltan versus non-Tahltan Stikine models for age-1.2, -1.3, -2.2, and -2.3 fish. All age-0. fish were assumed to be of non-Tahltan Stikine origin since no age-0. fish have been found in samples from Tahltan weir.

#### Estimation of the Stikine River Sockeye Run

The weir counts at Tahltan weir added to the number of Tahltan fish in the inriver sockeye salmon catches were used to estimate the total inriver run of Tahltan fish. A drift and set gill net inriver test fishery, operated by CDFO and ADF&G personnel, was located just above the U.S./Canada border (Figure 3). The CPUE of the drift gill net test fishery was used to estimate migratory timing, while stock composition was estimated from the combined catches of the drift and set test nets. The magnitude of the inriver run of the non-Tahltan Stikine stock group was estimated by mulitiplying the inriver run of Tahltan fish by the proportion of non-Tahltan fish in the test fish catch and dividing the sum by the proportion of Tahltan fish in the test fishery catch:

$$R_{1}. = \frac{R_{2}. * P'_{1}.}{P'_{2}.} \tag{4}$$

where: R<sub>1</sub>. = run size of non-Tahltan Stikine fish past the Canadian inriver test fishery,

R<sub>2</sub>. = run size of Tahltan fish past the Canadian inriver test fishery,

 $P'_1$ . = adjusted proportion of non-Tahltan Stikine fish in the season's test fishery catch, and

 $P'_2$ . = adjusted proportion of Tahltan fish in the season's test fishery catch. note  $P'_2$ . = 1 -  $P'_1$ .

and:

$$P'jt = Pjt * \frac{C_t}{\sum_{t=1}^{\Sigma} C_t}$$
 (5)

where: P'jt = adjusted proportion of total sockeye run belonging to stock j and occurring in week t,

Pjt = proportion of stock j in week t from test fishery catch analysis,

Ct = CPUE from test fishery in week t, and

N = number of weeks in fishing season.

The test fishery effort was 60 drifts per week in all weeks, except early August (week 32) when the effort was 50 drifts. The catch in week 32 was standardized to the level of other weeks by multiplying by 60/50.

#### Comparison of In- and Postseason Estimates

Adjusted in-season and postseason weekly stock composition estimates for Subdistricts 106-41 and 106-30 and for the Stikine River were compared to test whether the in-season estimates differed significantly from the postseason estimates for each fishery. The actual numbers of fish in the sample which were classified to each group in the in-season analysis were compared to those in the postseason analysis. Only the ages done in-season were compared. However, in some weeks time was insufficient to digitize a full sample in-season, and thus, the number of fish used in the postseason analysis was larger than that used in-season. Data was set up in a standard contingency table format and tested with the G statistic (log-likelihood ratio test) (Zar 1984).

#### RESULTS

The stock compositions of the sockeye salmon caught in Districts 106-41, 106-30, and 108 and in the Stikine River were estimated from mid-June through late September (statistical weeks 25 to 39). Of the 138,047 sockeye salmon harvested in Districts 106 and 108, 48% were of Alaska I origin, 34% of Alaska II, 15% of Nass/Skeena, 1% of Tahltan, 1% of non-Tahltan Stikine, and 1% of additional Stikine (combined) origin (Table 2). Of the Canadian lower Stikine River commercial catch of 6,138 (DFO 1987), 31% were of Tahltan and 69% were of non-Tahltan Stikine origin (Table 3). Model accuracies, determined from classification matrices (Appendix B), ranged from a low of 67% for the five-standard model to a high of > 90% for some of the two standard models (Table 4). The Alaska I and Alaska II groups tended to misclassify as each other, as did the Stikine, Tahltan and Nass/Skeena groups. In most models the Alaska II and Nass/Skeena groups had the lowest and the non-Tahltan Stikine standard had the highest misclassification rates. The in-season stock composition estimates were not significantly different from the post season estimates in most weeks.

#### Stock Composition of the Subdistrict 106-30 Catch

Stock composition by age class was estimated for the Subdistrict 106-30 sockeye harvest (Table 2). Of the estimated 57,262 sockeye salmon harvested in the drift gill net fishery in 1986, 84% were of Alaska I and Alaska II origin, 14% of Nass/Skeena origin, and 1.6% of transboundary Stikine River origin (combined from Appendix C.1). The peak harvests of Alaska I fish occured in early to mid-July; Alaska II fish peaked in mid-July to early August, and Nass/Skeena fish in early August (Figure 5). The Tahltan and non-Tahltan Stikine groups were only minor components with estimated contributions of 221 and 710 fish, respectively. The Alaska I group was harvested throughout the season and contributed >50% of the catch during mid-June through mid-July (weeks 26 to 29) (Figure 6). The Alaska II group dominated the catch in late July and early August, while the Nass/Skeena group comprised 10 and 20% of the catch throughout the season.

The CPUE (catch per boat day) of the Alaska I group was greater than 60 fish in early and mid-July (weeks 28 and 30). The peak CPUE of 74 Alaska II and 25 Nass/Skeena fish per boat day both occured during late July (week 31) (Appendix C.2). The weekly proportion of CPUE by group indicated that the migratory timings of the Alaska II and the Nass/Skeena groups were similar to each other and later than the Alaska I group in Subdistrict 106-30 (Figure 7). Little can be learned of the migratory timing of the Tahltan and non-Tahltan Stikine groups through the Subdistrict 106-30 fishery because of the extremely small catches of these stocks. A rough estimate of the migratory timing of the Stikine River sockeye stocks may be gleaned by combining data from this and previous years' stock composition estimates (Appendix D.1-4). Catches of the Tahltan group peak during late June-early July, while catches of the non-Tahltan Stikine group peak from mid-July to early August.

#### Stock Composition of the Subdistrict 106-41 Catch

Of the estimated 79,165 sockeye salmon harvested in Subdistrict 106-41 in 1987 (Table 2), 82% were of Alaska I and Alaska II origin, 17% of Nass/Skeena origin, and 1.8% of transboundary Stikine River origin (combined from Appendix C.3). Classifications were determined for each age class (Appendix C.3). The harvests of the Alaska I, Alaska II, and Nass/Skeena groups peaked mid-July, late July through early August, and early August, respectively (Figure 8). Stikine River stocks contributed only a small portion of the catch with the Tahltan contribution estimated at 1.5% and the non-Tahltan Stikine at 0.3%. Neither group contributed >1000 fish in any week, and no Stikine River fish were harvested after late July (week 30). The Alaska I group dominated the catch from mid-June through early July when they comprised an estimated 43-75% of the weekly catch and remained an important contributor through the remainder of the season (Figure 9). The Alaska II and Nass/Skeena groups comprised from 15-50% and 8-33%, respectively, of the weekly catches.

The estimated peak CPUE (catch per boat day) occured in mid-July (week 30) for the Alaska I, Alaska II, and non-Tahltan Stikine groups, in early July (week 28) for the Tahltan, and in early July and early August (weeks 28 and 32) for the Nass/Skeena groups. Peak CPUE's of 80, 61, and 34 fish for Alaska I, Alaska II, and Nass/Skeena, respectively, were much greater than those of Tahltan and non-Tahltan Stikine at 5 and 2 fish, respectively (Appendix C.4). The weekly proportion of CPUE, an indicator of migratory timing, peaked for all groups combined during mid-July (week 30), but, that of the individual groups all peaked in other weeks (Figure 10).

#### Stock Composition of the District 108 Catch

An estimated 37 fish of Alaska I, 14 of Alaska II, 0 of Nass/Skeena, 126 of Tahltan, 122 of non-Tahltan Stikine, and 124 fish of unknown origin were harvested in District 108 during mid-July (week 29) (Appendix C.5). The harvests during mid-June through early July (weeks 26-28) were estimated at 1063 Stikine combined and 134 Alaska combined.

#### Stock Composition of the Stikine River Catches

Stock contributions were estimated by age class for the Canadian commercial sockeye harvest in the lower Stikine River. The contributions of the Tahltan and non-Tahltan Stikine stock groups to the 6,138 drift and set gill net fishery harvest (Sandy Johnson, CDFO, personal communication) were estimated at 22.5% and 77.5% of the catch, respectively (Table 3 and Appendix E.1). Tahltan fish dominated the catch through mid-July (week 29) and non-Tahltan fish contributed the majority of the harvest after mid-July (week 30) (Figure 11).

A peak commercial catch per fishing day of 72 sockeye salmon occurred during early August (week 32) (Appendix E.2). The peak CPUE (catch per

fishing day) for Tahltan fish occured during mid-July (week 29) and that for non-Tahltan in early August (week 32).

Of the 1,667 sockeye caught in the Stikine River drift and set net test fishery an estimated 513 (30.8%) were of Tahltan and 1,154 (69.2%) were of non-Tahltan Stikine origin. As in the commercial catch, Tahltan fish dominated the catch through mid-July and non-Tahltan fish comprised the majority of the weekly catch thereafter (Table 3 and Appendix E.3) (Figure 12).

The peak standardized (60 drifts/week) test fish catch of 100 sockeye salmon occured in late July (week 30). The Tahltan group peaked in early July with 43 fish/drift week and the non-Tahltan group peaked in late July with 72 fish/drift week (Appendix E.4). The Tahltan group had a more compacted migratory timing than did the non-Tahltan fish (Figure 13.)

#### Stikine River Run Strength

Adjusted weekly proportions of Tahltan and non-Tahltan fish in the run were estimated using weekly proportions in the test fishery catch weighted by migratory timing determined from test fishery CPUE, as shown in equation (5). Summed over all weeks, this resulted in a total proportion of 0.341 Tahltan and 0.659 non-Tahltan fish in the inriver sockeye run (Appendix E.4). The total Canadian catch of Tahltan fish was 4,509 and the weir count for Tahltan escapement was 6,958, giving a Tahltan inriver run estimate of 11,467 (Table 5). These numbers, input into equation (4) provide an estimate of 22,161 for the non-Tahltan Stikine inriver sockeye run. The total sockeye salmon inriver run was therefore, 33,628 fish, which, combined with the catch of 3,655 Stikine River fish in Alaska's Districts 106 and 108 indicated a total Stikine River run of 37,283 sockeye salmon. The 90 Tahltan and 201 non-Tahltan fish caught in Alaska's District 106 and 108 test fisheries and the 513 Tahltan and 1154 non-Tahltan fish caught in the inriver test fisheries are not included in the above totals.

#### Comparison of In-season and Postseason Analysis

The in-season stock composition estimates were not significantly different from the postseason estimates (log-likelihood ratio analysis with  $\alpha$  = 0.05)(Table 6 and Appendix F). The in-season estimates did not differ significantly from the postseason estimates during late June and early July (weeks 26 and 28) in Subdistrict 106-30. In all weeks the in-season analysis indicated a greater relative abundance of the Alaska I group and a lesser relative abundance of the Alaska II group than did the postseason analysis (Appendix F.3). The in- and postseason estimates were not significantly different from late June through late July (weeks 27-30) in Subdistrict 106-41. However, as in Subdistrict 106-30, the inseason estimates of the Alaska I group were higher and of the Alaska II group were lower than the postseason estimates (Appendix F.7). There were no significant differences between the in- and postseason analyses of the Stikine River commercial catch.

#### DISCUSSION

Although the total sockeye catch in District 106 was close to the 1982-1986 average of 141,866 fish, the stock composition was substantially different from that of previous years (Appendix D). The actual and relative contribution of the Alaska groups to the harvest was the second highest and highest, respectively, since scale pattern analysis was initiated in 1982. As in 1986 a strong run of McDonald Lake fish was an important factor in the high contribution of the Alaska stocks. This stock has been exceedingly productive in recent years (1981-1987).

The stock composition of the District 108 sockeye catch could not be estimated by weekly samples expanded to catches since the catch was sampled only during mid-July (statistical week 29). An alternate method was developed since 71% of the catch, 1197 of 1690 fish, occurred before this time (statistical weeks 26-28). The commercial catch was sampled during this early period in 1986, and the test fishery catches in 1985 and 1986. Contributions of the individual stock groups were significantly different between years for a given week, however, the proportion contributed by the Stikine River as a whole (Stikine combined = Tahltan + non-Tahltan Stikine) was fairly constant. The relative weekly abundance of Stikine River fish in the sockeye catch was higher in 1985 than 1986, however, differences were not significant between years for weeks 25, 26, and 29 with log-likelihood ratio analysis,  $\alpha = 0.05$  (Table 1). Differences were significant during weeks 27 and 28, however, the total catches were small and the actual differences would have been <200 fish per week if the catches in 1986 had been as large as in 1985. Weekly interyear differences were either not significant or numerically small during 1985 and 1986 and for the one sampled period in 1987. Therefore, the contributions of Stikine River stock in each unsampled week in 1987 were estimated by averaging the contributions of Stikine River stocks during the same week during the other years. Based on the stock compositions in previous years, the remaining fish were most likely of Alaska I origin.

Both the actual and relative contribution of the Stikine River stocks to the harvest in Alaska's Districts 106 and 108 were the lowest recorded (1982-1987). The low run in 1987 of the Tahltan stock group, 12,969 fish (82.6% age 1.3), was unexpected in light of the moderate, 28,257 fish, escapement in 1982. The low abundance of the age-1.2 fish, 14 out of the 797 (1.8%) ageable escapement scales, indicated a weak recruitment from the 1983 escapement (21,256 fish) as well. Although there are currently few data points, it appears that sibling forecasting may be an appropriate means of predicting future Tahltan runs. The low return of the non-Tahltan Stikine stock group, was also unexpected. However, the variances around the escapement estimates for this group are very large and a spawner-recruit curve is difficult to develop. The egg to juvenile survival of the sockeye salmon that hatch and rear in the mainstem and side channels of the Stikine River would most likely be more heavily influenced by environmental factors, particularly water level, than would lake residents. Thus, the number of recruits may not be closely correlated to the number of spawners. The Canadian commercial fishery, initiated in 1979, may also have had a negative impact on the run. However, since 1986, also a low run, was the first run when all contributing parent years had been subjected to major harvests in the fishery, no real conclusion can be drawn.

Two-stock standards were used for the Tahltan/non-Tahltan Stikine stock separation in the inriver test fishery and commercial catches. The numbers of samples used in the standards for fish other than age-1.3 were small, and therefore, variances in final stock composition estimates were relatively large compared to those of the age-1.3 fish.

The in-season and postseason stock composition comparison is a measure of interannual variation in scale patterns since the standards used are from 2 different years. Much of the differences in the in-season and postseason analyses can be expained by slight differences in the growth of the fish that returned in each year. For example, the means of both the freshwater and first marine scale zones of Alaska I age-1.3 fish were smaller in 1987 than in 1986, while the mean freshwater zone of the Alaska II fish was larger in 1987 than 1986. Since the freshwater zone of the Alaska I fish tends to be larger than that of the Alaska II fish, the 1986 model tended to overestimate the contributions of the Alaska I group and underestimate those of the Alaska II group in the 1987 sockeye catch. Similar trends were observed for other age fish and other stock groups; however, the changes are usually small and balance each other such that the in-season analysis still adequately reflects the weekly stock compositions.

The test fishery in the Stikine River was used to estimated both the stock composition and the run timing of the inriver sockeye run. The test fishery was used rather than the commercial catch since it fished throughout each week (5 to 6 d as opposed to 1 to 2 d for the commercial fishery), it was located below the known major spawning areas (some of the commercial fishery extends upriver of spawning grounds), and it was run in a standardized manner. The stock composition was estimated for the combined drift and set net test catches in order to get sufficiently large sample sizes for weekly estimates and to minimize the potential bias of gear selectivity. The migratory timing was estimated from the drift gill net CPUE since drift net catches appear to be less affected than set net catches by changes in water level and since the daily CPUE from multiple drifts would less affected by a fouled net than would the CPUE from a single day long set.

Knowledge of the migratory timing of the stock groups in mixed stock fisheries is necessary if managers wish to allow differential harvest rates on the various stock groups. The migratory timing of a stock group through a commercial fishery district can be estimated from the weekly proportion of the total CPUE attributed to that stock group. Although the CPUE may be affected by several variables including gear competition and efficiency, weather conditions, rate of fish passage, fishing expertise, or availability of other species, in some situations it is the best or only method available for estimating migratory timing.

Analysis of scale patterns enable us to estimate the contributions of major stock groups to fisheries in Districts 106-41, 106-30, and 108 and in the Stikine River. The in-season stock identification program provided managers with timely estimates of relative stock strengths which were used in making fishery extension or closure decisions. In-season exchange of stock

composition estimates, catches and CPUE's, and escapement data, between the CDFO and the ADF&G allowed personnel to cooperate in managing the Stikine River sockeye salmon as mandated in the U.S./Canada Pacific Salmon Treaty. Research on stock separation techniques is an ongoing process. Cooperative research programs between the U.S. and Canada should enable us to further refine stock composition estimates in the future.

#### LITERATURE CITED

- Anas, R.E., and S. Murai. 1969. Use of scale characters and a discriminant function for classifying sockeye salmon (*Oncorhynchus nerka*) by continent of origin. International North Pacific Fisheries Commission, Bulletin 26:157-192.
- Clutter, R., and L. Whitesel. 1956. Collection and interpretation of sockeye salmon scales. Bulletin International Pacific Salmon Fisheries Commission, No. 9, New Westminster, British Columbia, Canada.
- Cook, R.C., and G.E. Lord. 1978. Identification of stocks of Bristol Bay sockeye salmon (*Oncorhynchus nerka*), by evaluating scale patterns with a polynomial discriminant method. Fisheries Bulletin 76(2):415-423.
- PSC (The Pacific Salmon Commission). 1988. U.S./Canada Northern Boundary Area Salmon Fisheries Management Report and 1988 Preliminary Expectations. Northern Boundary Technical Committee Report TCNB (88)-1, Vancouver, British Columbia, Canada.
- CDFO (Canadian Department of Fisheries and Oceans). 1986. Fraser River, northern B.C. and Yukon Division summary review of 1986 salmon fisheries and returns. Report to the Pacific Salmon Commission, Vancouver, British Columbia, Canada.
- Enslein, K., A. Ralston, and H. S. Wilf. 1977. Statistical methods for digital computers. John Wiley and Sons, Inc., New York.
- Fisher, R. A. 1936. The use of multiple measurements in taxonomic problems. Annal Eugenics 7:179-188.
- Gilbert, E.S. 1969. The effect of unequal variance-covariance matrices on Fisher's linear discriminant function. Biometrics 25(3):505-515.
- Habbema, J.D.F., and J. Hermans. 1977. Selection of variables in discriminant function analysis by F-statistic and error rate. Technometrics 19(4):487-493.
- INPFC (International North Pacific Fisheries Commission). 1963. Annual Report 1961, Vancouver, British Columbia.
- Issacson, S.L. 1954. Problems in classifying populations. Pages 107-117 in O. Kempthorne, T.A. Bancroft, J.W. Gowen, and J.L. Lush, editors. Statistics and mathematics in biology. Iowa State College Press, Ames.
- Jensen, K.A., G.T. Oliver, and I.S. Frank. *In press*. Contributions of principal sockeye salmon stock groups to catches in Southeast Alaska's Districts 106 and 108 and Canada's Stikine River fisheries, 1986, estimated with scale pattern analysis. Alaska Department of Fish and Game, Division of Commercial Fisheries, Technical Fisheries Report, Juneau.

#### LITERATURE CITED (Continued)

- Krzanowski, W. J. 1977. The performance of Fisher's linear discriminant function under non-optimal conditions. Technometrics 19(2):191-200.
- Lachenbruch, P. A. 1967. An almost unbiased method of obtaining confidence intervals for the probability of misclassification in discriminant analysis. Biometrics 23(4):639-645.
- Lachenbruch, P. A., C. Sneeringer, and L. T. Revo. 1973. Robustness of the linear and quadratic discriminant function to certain types of non-normality. Communications in Statistics 1(1)39-56.
- Marshall, S. L., and nine coauthors. 1987. Application of scale pattern analysis to the management of Alaska's sockeye salmon (*Oncorhynchus nerka*) fisheries. Canadian Special Publications in Fisheries and Aquatic Science 96:307-326.
- Marshall, S. L., and three coauthors. 1984. The accuracy of scale pattern analysis in separating major stocks of sockeye salmon (*Oncorhynchus nerka*) from southern southeastern Alaska and Northern British Columbia. Alaska Department of Fish and Game, Division of Commercial Fisheries, Informational Leaflet 230, Juneau.
- McGregor, A.J. 1983. Age, sex, and size of sockeye salmon (*Oncorhynchus nerka* Walbaum) catches and escapements in Southeastern Alaska in 1982. Alaska Department of Fish and Game, Division of Commercial Fisheries, Technical Data Report 100, Juneau.
- McGregor, A.J., S.A. McPherson, and J.E. Clark. 1984. Abundance, age, sex, and size of sockeye salmon (*Oncorhynchus nerka* Walbaum) catches and escapements in Southeastern Alaska in 1983. Alaska Department of Fish and Game, Division of Commercial Fisheries, Technical Data Report 132, Juneau.
- McGregor, A.J., and S.A. McPherson. 1985. Abundance, age, sex, and size of sockeye salmon (*Oncorhynchus nerka* Walbaum) catches and escapements in Southeastern Alaska in 1984. Alaska Department of Fish and Game, Division of Commercial Fisheries, Technical Data Report 166, Juneau.
- McPherson, S. A., and A. J. McGregor. 1986. Abundance, age, sex, and size of sockeye salmon (*Oncorhynchus nerka* Walbaum) catches and escapements in Southeastern Alaska in 1985. Alaska Department of Fish and Game, Division of Commercial Fisheries, Technical Data Report 188, Juneau.
- McPherson, S.A., F.E. Bergander, and A.J. McGregor. 1988a. Abundance, age, sex, and size of sockeye salmon catches and escapements in Southeast Alaska in 1986. Alaska Department of Fish and Game, Division of Commercial Fisheries, Technical Fisheries Report 88-08, Juneau.

#### LITERATURE CITED (Continued)

- McPherson, S.A., M.A. Olsen, and A.J. McGregor. 1988b. Abundance, age, sex, and size of sockeye salmon catches and escapements in Southeast Alaska in 1987. Alaska Department of Fish and Game, Division of Commercial Fisheries, Technical Fisheries Report 88-12, Juneau.
- Mosher, K. H. 1968. Photographic atlas of sockeye salmon scales. Fishery Bulletin 67(2):243-279.
- Narver, D. W. 1963. Identification of adult red salmon groups by lacustrine scale measurement, time of entry, and spawning characteristics. M.S. Thesis, University of Washington, Seattle.
- Oliver, G.T., and four coauthors. 1984. Estimated contribution from Alaska and Canada stocks to the catches of sockeye salmon in southern Southeast Alaska, 1982 and 1983, based on scale pattern analysis. Alaska Department of Fish and Game, Division of Commercial Fisheries, Technical Data Report 137, Juneau.
- Oliver, G.T. and S.L. Walls. 1985. Estimated contribution from Alaska and Canada stocks to the catches of sockeye salmon in southern Southeast Alaska, 1984, based on the analysis of scale patterns. In ADF&G (Alaska Department of Fish and Game) Section Report in 1984 Salmon Research Conducted in Southeast Alaska by the Alaska Department of Fish and Game in conjunction with National Marine Fisheries Service Auke Bay Laboratory for Joint U.S.-Canada Interception Studies. Division of Commercial Fisheries, Final Report, Contract Report WASC-84-00179, Douglas, Alaska.
- Oliver, G.T. and K.A. Jensen. 1986. Estimated contribution of Alaskan, Canadian, and Transboundary stocks to the catches of sockeye salmon in southern Southeast Alaska, 1985, based on analysis of scale patterns. In ADF&G (Alaska Department of Fish and Game) Section Report in 1985 Salmon Research Conducted in Southeast Alaska by the Alaska Department of Fish and Game in Conjunction with the National Marine Fisheries Service Auke Bay Labratory for Joint U.S./Canada interception Studies, Division of Commercial Fisheries, Final Report, Contract Report 85-ABC-00142, Douglas, Alaska.
- Pella, J. and T. Robertson. 1979. Assessment of composition of stock mixtures. Fishery Bulletin 72(2):387-389.
- Ryan, P. and M. Christie. 1976. Scale reading equipment. Fisheries and Marine Service, Canada Technical Report PAC/T-75-8, Nanaimo, British Columbia.
- Seber, G. 1982. The estimation of animal abundance and related parameters. Charles Griffin & Company Ltd., London.
- TTC (Transboundary Technical Committee). 1987. Report of the Pacific Salmon Commission Technical Committee, February, 1987. Unpublished report prepared for members of the Pacific Salmon Commission and Northern Panel, Vancouver, British Columbia.

# LITERATURE CITED (Continued)

Zar, J. Z. 1984. Biostatistical analysis. Prentice-Hall, Inc., Englewood Cliffs, New Jersey.

TABLES AND FIGURES

Table 1. Log-likelihood (G) values for a comparison of estimates in Alaska's District 108 commercial and test drift gill net fisheries, 1985-1987.

			Numb	er of Fis	h b	
Stat. Week <sup>a</sup>	Fishery	Proportion Stikine	Stikine	Non- Stikine	Total	G
Week 25	1985 Test	0.802	54	13	67	
	1986 Com.	0.750	23	8	30	
	Total		76	21	97	0.324
Week 26	1985 Test	0.866	48	7	55	
	1986 Test	0.832	94	19	113	
	1986 Com.	0.786	11	3	14	
	Total		153	29	182	0.627
Week 27	1985 Test	0.968	56	2	58	
	1986 Test	0.819	107	24	130	
	Total		163	25	188	9.405
Week 28	1985 Test	0.996	67	1	68	
	1986 Test	0.798	101	26	126	
	Total		167	27	194	17.802
Week 29	1985 Test	0.922	65	5	70	
	1986 Test	0.810	170	40	210	
	1986 Com.	0.829	248	51	299	
	Total		483	96	579	5.664

Critical values:  $x^2$  0.05,1 = 3.841,  $x^2$  0.05,2 = 5.991

Ho: The interyear stock composition estimates are independent for a given week.

b Numbers are from unexpanded samples.

Week 25 starting date, June 16, 15, 14 in 1985, 1986, 1987, respectively.

Table 2. Estimated contributions of sockeye salmon stock groups to Alaska's District 106 and 108 commercial drift gill net fisheries, 1987.

		Catch	by Distr	ict		**
Dates	Group	106-30	106-41	108 a	Total	Percent
6/21-6/27 Week 26	Ak. I Ak. II Nas/Ske Tahltan Stikine Sti. Com Unknown Total	809 312 33 135 14 b.	2,886 619 289 51 0	160 29 189	3,695 931 322 186 14 160 29 5,337	0.69 0.17 0.06 0.03 0.00 0.03 0.01
6/28-7/04 Week 27	Ak. I Ak. II Nas/Ske Tahltan Stikine Sti. Com Unknown Total	1,511 1,046 358 4 0 b.	5,422 996 996 100 0	219 26 2 <b>4</b> 5	6,933 2,042 1,354 104 0 219 26	0.65 0.19 0.13 0.01 0.00 0.02 0.00
7/05-7/11 Week 28	Ak. I Ak. II Nas/Ske Tahltan Stikine Sti. Com Unknown Total	4,108 637 805 6 14 b.	6,445 2,951 4,962 774 43	68 <b>4</b> 75 759	10,553 3,588 5,767 780 57 684 75 21,504	0.49 0.17 0.27 0.04 0.00 0.03
7/12-7/18 Week 29	Ak. I Ak. II Nas/Ske Tahltan Stikine Unknown Total	5,714 1,120 1,035 76 580 8,525	9,927 2,089 1,629 116 0	37 14 0 126 122 124 299	15,678 3,223 2,664 318 702 22,585	0.69 0.14 0.12 0.01 0.03
7/19-7/25 Week 30	Ak. I Ak. II Nas/Ske Tahltan Stikine Total	5,007 4,486 1,147 0 10,640	7,208 5,451 1,043 114 215 14,031		12,215 9,937 2,190 114 215 24,671	0.50 0.40 0.09 0.00 0.01
7/26-8/01 Week 31	Ak. I Ak. II Nas/Ske Tahltan Stikine Total	3,007 7,276 2,483 0 0 12,766	4,418 4,568 1,246 0 10,232		7,425 11,844 3,729 0 0 22,998	0.32 0.52 0.16 0.00 0.00
8/02-8/08 Week 32	Ak. I Ak. II Nas/Ske Tahltan Stikine Total	3,074 7,196 1,683 0 0 11,953	3,306 5,494 2,275 0 0 11,075		6,380 12,690 3,958 0 0 23,028	0.28 0.55 0.17 0.00 0.00
8/09-9/19 Wks 33-38	Ak. I Ak. II Nas/Ske Tahltan Stikine Unknown Total	1,858 1,150 476 0 102	1,804 998 730 0 0	4 4	3,662 2,148 1,206 0 102 7,122	0.51 0.30 0.17 0.00 0.01
Fishery Total	Ak. I Ak. II Nas/Ske Tahltan Stikine Sti. Com Unknown Total	25,088 23,223 8,020 221 710	41,416 23,166 13,170 1,155 258	37 14 0 126 122 1063 258 1,620	66,541 46,403 21,190 1,502 1,090 1,063 258 138,047	0.48 0.34 0.15 0.01 0.01 0.01

The catch in weeks 26-28 was estimated for total Stikine River (Tahltan and non-Tahltan Stikine), the unknown fish are of Alaska I, Alaska II, or of Nass/Skeena origin.

Table 3. Estimated contributions of Tahltan and non-Tahltan sockeye salmon stock groups to the Stikine River test fishery and to Canada's lower river commercial fishery, 1987.

		Commerc	ial Catch	Test	Fishery
Dates	Group	Total	Percent	Total	Percent
6/28-7/04 Week 27	Tahltan Non-Tahltan Total	133 46 179	74.3 25.7	52 8 60	86.7 13.3
7/05-7/11 Week 28	Tahltan Non-Tahltan Total	148 21 169	87.6 12.4	162 47 209	77.5 22.5
7/12-7/18 Week 29	Tahltan Non-Tahltan Total	615 311 926	66.4 33.6	166 122 288	57.6 42.4
7/19-7/25 Week 30	Tahltan Non-Tahltan Total	264 820 1,084	24.4 75.6	82 211 293	28.0 72.0
7/26-8/01 Week 31	Tahltan Non-Tahltan Total	50 391 441	11.3 88.7	25 258 283	8.8 91.2
8/02-8/08 Week 32	Tahltan Non-Tahltan Total	125 2,327 2,452	5.1 94.9	25 244 269	9.3 90.7
8/09-8/15 Week 33	Tahltan Non-Tahltan Total	22 527 549	4.0 96.0	1 162 163	0.6 99.4
8/16-9/26 Wks 34-39	Tahltan Non-Tahltan Total	23 315 338	6.8 93.2	0 102 102	0.0
Fishery Totals	Tahltan Non-Tahltan Total	1,380 4,758 6,138	22.5 77.5	513 1,154 1,667	30.8 69.2

Table 4. Mean classification accuracies from linear discriminant function models used to classify sockeye salmon harvested in Alaska's Districts 106 and 108 and Canada's Stikine River gill net fisheries, 1987.

	Mean Clas	sification	Accuracy	by Age
Stock Groups	1.2	1.3	2.2	2.3
Alaska I vs Alaska II vs Nass/Skeens vs Tahltan vs Stikine	3	0.670		
Alaska I vs Alaska II vs Nass/Skeens vs Tahltan	a	0.753		0.711
Alaska I vs Alaska II vs Nass/Skeens vs Stikine	<b>a</b>	0.707		
Alaska I vs Alaska II vs Tahltan vs Stikine		0.674		
Alaska I vs Alaska II vs Nass/Skeen	a 0.779	0.795		0.749
Alaska I vs Alaska II vs Tahltan		0.807		0.761
Alaska I vs Alaska II vs Stikine		0.761		
Alaska I vs Nass/Skeena vs Tahltan		0.726		
Alaska I vs Nass/Skeena vs Stikine		0.772		
Alaska I vs Tahltan vs Stikine		0.748		
Alaska I vs Alaska II	0.835			0.738
Alaska I vs Nass/Skeena	0.936		0.924	0.933
Alaska II vs Nass/Skeena				0.916
Tahltan vs Stikine	0.897	0.884	0.971	0.814

Table 5. Catch and escapement of Stikine River sockeye salmon, 1987.

Area	Combineda	Tahltan	non- Tahltan	Total
Canadian Catch				
Telegraph Creek Food Fisher Upper River Commercial Lower River Commercial	гy	2,681 448 1,380		2,979 498 6,138
Total Canadian Catch	***************************************	4,509	5,106	9,615
Alaskan Catch				
District 106 and 108	1,063	1,502	1,090	3,655
Total Catch	1,063	6,011	6,196	13,270
Spawning Escapement		6,958	17,055	24,013
Total Inriver Run		11,467	22,161	33,628
Total Stikine River Run		12,969	23,251	37,283
Test Fishery Catches b				
Canada's Inriver Alaska's District 106 d Alaska's District 108 d		513 42 48	1,154 0 201	1,667 42 249

Combined Tahltan and non-Tahltan Sitkine from District 108.
Test fishery catches not included in total run size estimation by agreement of Transboundary Technical Committee agreement.

agreement.

c Not sampled, weekly stock composition estimates from the commercial catches applied to weekly test fishery catches. Not sampled, weekly stock composition estimates from test fisheries in previous years applied to 1987 catches.

Table 6. Log-likelihood (G) values for the comparison of weekly in-season and postseason stock composition estimates for sockeye salmon harvested in Alaska's District 106 and Canada's Stikine River commercial gill net fisheries, 1987.

Stat. Week	Dates	G	Р	Rejegt Ho
106-41	Critical value	= 9.488		
26 27 28 29 30 31	6/21-6/27 6/28-7/04 7/05-7/11 7/12-7/18 7/19-7/25 7/26-8/01 8/02-8/08	19.989 2.595 8.698 3.590 4.959 14.267 30.194	P < 0.001 0.500 < P < 0.750 0.050 < P < 0.100 0.250 < P < 0.500 0.250 < P < 0.500 0.010 < P < 0.005 P < 0.001	yes no no no yes yes
Season	total	117.443	P < 0.001	yes
106-30	Critical value	= 9.488		
26 27 28 29 30 31 32	6/21-6/27 6/28-7/04 7/05-7/11 7/12-7/18 7/19-7/25 7/26-8/01 8/02-8/08	8.438 17.424 1.652 12.792 93.983 33.225 20.958	0.050 < P < 0.100 0.005 < P < 0.010 0.750 < P < 0.900 0.025 < P < 0.050 P < 0.001 P < 0.001 P < 0.001	no yes yes yes yes
Season	total	159.939	P < 0.001	yes
Stikine	e Critical value	e = 3.841		
27 28 29 30 31 32	6/28-7/04 7/05-7/11 7/12-7/18 7/19-7/25 7/26-8/01 8/02-8/08	0.335 1.839 0.299 1.324 0.884 0.420	0.500 < P < 0.750 0.100 < P < 0.250 0.500 < P < 0.750 0.100 < P < 0.250 0.250 < P < 0.500 0.500 < P < 0.750	no no no no no
Season	total	0.010	0.900 < P < 0.950	no

A Ho: The stock composition estimates are independent of the type of analysis (ie. in-season or postseason).




Figure 1. Southeast Alaska, northern British Columbia, and the transboundary Stikine River.




Figure 2. Major sockeye salmon systems of Southeast Alaska. Numbers identify lakes where scale samples have been collected and  $\mathbf x$  indicates systems where scales were collected in 1987.




Figure 3. The transboundary Stikine River, major tributaries, and fishery areas.




Figure 4. Typical scale for age-2. and -1. sockeye salmon with zones used for scale pattern analysis delineated.




Figure 5. Weekly harvest of major sockeye salmon stock groups in Alaska's Subdistrict 106-30 drift gill net fishery, 1987.




Figure 6. Proportion of each major sockeye salmon stock group in the weekly catch in Alaska's Subdistrict 106-30 drift gill net fishery, 1987.




Figure 7. Migratory timing of major sockeye salmon stock groups as indicated by the weekly proportion of a total stock group CPUE in Alaska's Subdistrict 106-30 drift gill net fishery, 1987.




Figure 8. Weekly harvest of major sockeye salmon stock groups in Alaska's Subdistrict 106-41 drift gill net fishery, 1987.




Figure 9. Proportion of each major sockeye salmon stock group in the weekly catch in Alaska's Subdistrict 106-41 drift gill net fishery, 1987.




Figure 10. Migratory timing of major sockeye salmon stock groups as indicated by the weekly proportion of a total stock group CPUE in Alaska's Subdistrict 106-41 drift gill net fishery.




Figure 11. Weekly harvest of Tahltan and Stikine sockeye salmon and relative abundance of the two stock groups in Canada's lower Stikine River commercial fishery, 1987.

STATISTICAL WEEK




Figure 12. Weekly catch of Tahltan and Stikine sockeye salmon and relative abundance of the two stock groups in the Stikine River test fishery, 1987.




Figure 13. Migratory timing of the Tahltan and Stikine sockeye stock groups as indicated by the weekly proportion of total stock group CPUE in the Stikine River test fishery, 1987.

**APPENDICES** 

Appendix A.1. Sample sizes from the in-season sockeye salmon stock composition estimates from Alaska's Districts 106 and 108 and Canada's Stikine River commercial gill net fisheries, 1987.

Charle			Samp	le Size b	y Age Gro	up	
Stat. Week	Date	1.2	1.3	2.2	2.3	0.	Total
106-30							
26	6/21-6/27	0	62	0	0	0	62
27	6/28-7/04	20	100	0	25	0	145
28	7/05-7/11	62	100	0	76	0	238
29	7/12-7/18	38	100	0	90	0	228
30	7/19-7/25	48	99	0	86	0	233
31	7/26-8/01	20	87	0	52	0	159
32	8/02-8/08	30	100	0	71	0	201
Totals		218	648	0	400	0	1266
106-41							
26	6/21-6/27	45	209	0	65	0	319
27	6/28-7/04	47	192	0	56	0	295
28	7/05-7/11	53	187	0	77	0	317
29	7/12-7/18	66	193	0	79	0	338
30	7/19-7/25	40	199	0	102	0	341
31	7/26-8/01	47	187	0	100	0	334
32	8/02-8/08	43	141	0	100	0	284
Totals		341	1308	0	579	0	2228
108							
29	7/12-7/18	0	57	0	0	10	67
Totals		0	57	0	0	10	67
Stikine,	Canadian						
27	6/28-7/04	0	39	0	0	1	40
28	7/05-7/11	0	68	0	0	1	69
29	7/12-7/18	0	269	0	42	22	333
30	7/19-7/25	0	236	0	42	51	329
31	7/26-8/01	0	91	0	21	25	137
32	8/02-8/08	0	100	0	25	64	189
Totals		0	803	0	130	164	1097

Appendix A.2. Sample sizes from the postseason sockeye salmon stock composition estimates from Alaska's Districts 106 and 108 and Canada's Stikine River gill net fisheries, 1987.

Stat			Sample	le Size by Age Group <sup>a</sup>			
Stat. Week	Date	1.2	1.3	2.2	2.3	0.	Total
106-30	Commercial						
26 27 28 29 30 31 32 33–38	6/21-6/27 6/28-7/04 7/05-7/11 7/12-7/18 7/19-7/25 7/26-8/01 8/02-8/08 8/09-9/19	26 62 47 55 41 49 71	62 100 100 100 99 87 100	37 52 37 36 38 52 79	40 76 100 98 100 71	0 0 0 0 0	62 203 290 284 288 266 272 350
Totals		351	748	331	585	0	2015
106-41	Commercial						
26 27 28 29 30 31 32 33–38	6/21-6/27 6/28-7/04 7/05-7/11 7/12-7/18 7/19-7/25 7/26-8/01 8/02-8/08 8/09-9/19	45 47 53 66 40 47 43	209 192 187 193 199 187 141	47 49 38 29 40 52 64 98	65 56 77 79 102 100 100	0 0 0 0 0	366 344 355 367 381 386 348 394
Totals		410	1435	417	679	0	2941
108 Com	mercial						
29	7/12-7/18	0	57	0	0	10	67
Totals		0	57	0	0	10	67
Stikine	Commercial						
27 28 29 30 31 32 33 34 35-39	6/28-7/04 7/05-7/11 7/12-7/18 7/19-7/25 7/26-8/01 8/02-8/08 8/09-8/15 8/16-8/22 8/23-9/19	12 36 51 35 102 48 28	39 68 269 236 91 100 99 56 33	14 17 15 12	7 42 42 21 25 17	1 22 51 25 64 32 12	40 88 383 397 172 306 208 96 43
Totals		312	991	58	154	218	1733
Stikine	Test						
26-27 28 29 30 31 32 33 34-37	6/21-7/04 7/05-7/11 7/12-7/18 7/19-7/25 7/26-8/01 8/02-8/08 8/09-8/15 8/16-9/12	17 20 23 27 25	47 146 147 160 139 119 87 45	1 <b>4</b> 9	22 32 21 20 14 16	3 5 19 33 35 26 15	50 173 215 248 226 186 143 56
Totals		112	890	23	125	147	1297

The samples for some ages in some weeks were too small to analyze and were combined with adjacent weeks and weighted by relative catches.

Appendix A.3. Scale variables used for age-1.2, 1.3, 2.2, and 2.3 sockeye salmon scale pattern analysis.

Variable Number	e Description
	First Freshwater (FW) Annular Zone
1	Number of circuli in the zone
2	Distance across the zone
3	Distance: scale focus (CO) to the second circulus in zone (C2)
4	Distance: C0 to C4
5	Distance: C0 to C6
6	Distance: C0 to C8
7	Distance: C2 to C4
8	Distance: C2 to C6
9	Distance: C2 to C8
10	Distance: C4 to C6
11	Distance: C4 to C8
12	Distance: fourth from the last circulus of zone to end of zone
13	Distance: second from the last circulus of zone to end of zone
14	Distance: C2 to end of zone
15	Distance: C4 to end of zone
16	Relative Distance: (Variable #3)/(Variable #2)
17	Relative Distance: (Variable #4)/(Variable #2)
18	Relative Distance: (Variable #5)/(Variable #2)
19	Relative Distance: (Variable #6)/(Variable #2)
20	Relative Distance: (Variable #7)/(Variable #2)
21	Relative Distance: (Variable #8)/(Variable #2)
22	Relative Distance: (Variable #9)/(Variable #2)
23	Relative Distance: (Variable #10)/(Variable #2)
24	Relative Distance: (Variable #11)/(Variable #2)
25	Relative Distance: (Variable #12)/(Variable #2)
26	Relative Distance: (Variable #13)/(Variable #2)
27	Average Distance between circuli: (Variable #2)/(Variable #1)
28	Number of circuli in the first 3/4 of the zone
29	Maximum distance between two adjacent circuli in the zone
30	Relative Distance: (Variable #29)/(Variable #2)
	Second Freshwater (FW) Annular Zone
31	Number of circuli in the zone
32	Distance across the zone
33	Distance: end first annular zone (E1FW) to second circulus in zone
34	Distance: E1FW to C4
35	Distance: E1FW to C6
36	Distance: E1FW to C8
37	Distance: C2 to C4
38	Distance: C2 to C6
39	Distance: C2 to C8

-Continued-

Variable Number	e Description
40	Distance: C4 to C6
41	Distance: C4 to C8
42	Distance: fourth from the last circulus of zone to end of zone
43	Distance: second from the last circulus of zone to end of zone
44	Distance: C2 to end of zone
45	Distance: C4 to end of zone
46	Relative Distance: Variable #33/Variable #32
47	Relative Distance: Variable #34/Variable #32
48	Relative Distance: Variable #35/Variable #32
49	Relative Distance: Variable #36/Variable #32
50	Relative Distance: Variable #37/Variable #32
51	Relative Distance: Variable #38/Variable #32
52	Relative Distance: Variable #39/Variable #32
53	Relative Distance: Variable #40/Variable #32
54	Relative Distance: Variable #41/Variable #32
55	Relative Distance: Variable #42/Variable #32
56	Relative Distance: Variable #43/Variable #32
57	Average Distance between circuli: Variable 32/Variable 31
58	Number of circuli in first 3/4 of zone
59	Maximum distance between two adjacent circuli in the zone
60	Relative Distance: Variable 59/Variable 32  Freshwater Plus Growth (PG)
61	Number of circuli in the zone
62	Distance across the zone
	Combined Freshwater Zones
63	Total number annular circuli, Variable 1 + Variable 31
64	Total distance across freshwater zones, Variable 2 + Variable 32
65	Total number of circuli in the combined zones, NC1FW+NC2FW+NCPG
66	Total distance across the combined zones, S1FW+S2FW+SPGZ
67	Relative Distance: (Variable #2)/(Variable #66)
	First Marine (C) Annular Zone
70	Number of circuli in the zone
71	Distance across the zone
72	Distance: end of FW (EFW) to the third circulus in zone (C3)
73	Distance: EFW to C6
74	Distance: EFW to C9
75	Distance: EFW to C12
76	Distance: EFW to C15

-Continued-

Appendix A.3. (p 3 of 3)

Variable Number	Description
77	Distance: C3 to C6
78	Distance: C3 to C9
79	Distance: C3 to C12
80	Distance: C3 to C15
81	Distance: C6 to C9
82	Distance: C6 to C12
83	Distance: C6 to C15
84	Distance: C9 to C15
85	Distance: sixth from the last circulus of zone to end of zone
86	Distance: third from the last circulus of zone to end of zone
87	Distance: C3 to end of zone
88	Distance: C9 to end of zone
89	Distance: C15 to end of zone
90	Relative Distance: (Variable #72)/(Variable #71)
91	Relative Distance: (Variable #73)/(Variable #71)
92	Relative Distance: (Variable #74)/(Variable #71)
93	Relative Distance: (Variable #75)/(Variable #71)
94	Relative Distance: (Variable #76)/(Variable #71)
95	Relative Distance: (Variable #77)/(Variable #71)
96	Relative Distance: (Variable #78)/(Variable #71)
97	Relative Distance: (Variable #79)/(Variable #71)
98	Relative Distance: (Variable #80)/(Variable #71) Relative Distance: (Variable #81)/(Variable #71)
99 100	Relative Distance: (Variable #81)/(Variable #71) Relative Distance: (Variable #82)/(Variable #71)
100	Relative Distance: (Variable #83)/(Variable #71)
101	Relative Distance: (Variable #05)/(Variable #71)  Relative Distance: (Variable #84)/(Variable #71)
102	Relative Distance: (Variable #85)/(Variable #71)
104	Relative Distance: (Variable #86)/(Variable #71)
105	Relative Distance: (Variable #87)/(Variable #71)
106	Number of circuli in the first 1/2 of the zone
107	Maximum distance between two adjacent circuli in the zone
108	Relative Distance: (Variable #107)/(Variable #71)

Appendix B.1. Classification matrices for linear discriminant function models used to classify age-1.2 sockeye salmon from Alaska's Districts 106 and 108 and from Canada's Stikine River gill net fisheries, 1987.

Actual Group	Sample		
of Origin	size	Classified Group	of Origin
3 way model :		Ak. I Ak. II	Nas/Ske
Ak. I	212	0.750 0.189	0.061
Ak. II	58	0.138 0.759	0.103
Nas/Ske	208	0.053 0.120	0.827
Mean Proportion	Correctly Classified		0.779
2 way model :		Ak. I Ak. II	
Ak. I	212	0.825 0.175	5
Ak. II	58	0.155 0.845	
Mean Proportion	Correctly Classified		0.835
2 way model :		Ak. I	Nas/Ske
Ak. I	212	0.915	0.085
Nas/Ske	208	0.043	0.957
Mean Proportion	Correctly Classified		0.936
2 way model :		Tahltan	Stikine
Tahltan	13	1.000	0.000
Stikine	29	0.207	0.793
Mean Proportion (	Correctly Classified		0.897

Appendix B.2. Classification matrices for linear discriminant function models used to classify age-1.3 sockeye salmon from Alaska's District 106 and 108 and Canada's Stikine River gill net fisheries, 1987.

Actual Group of Origin	Sample Size	C	Classifie	d Group	of Origin	
5 way model :		Ak. I	Ak. II	Nas/Ske	Tahltan	Stikine
Ak. I Ak. II Nas/Ske Tahltan Stikine	190 200 200 200 102	0.558 0.120 0.025 0.090 0.059	0.153 0.815 0.060 0.000 0.157	0.105 0.005 0.745 0.120 0.167	0.105 0.000 0.095 0.705 0.088	0.079 0.060 0.075 0.085 0.529
Mean Proportion C	orrectly Cla	assified				0.670
4 way model :		Ak. I	Ak. II	Nas/Ske	Tahltan	
Ak. I Ak. II Nas/Ske Tahltan	190 200 200 200	0.611 0.170 0.025 0.120	0.158 0.820 0.075 0.000	0.116 0.010 0.795 0.095	0.116 0.000 0.105 0.785	
Mean Proportion C	orrectly Cla	assified				0.753
4 way model :		Ak. I	Ak. II	Nas/Ske		Stikine
Ak. I Ak. II	190 200	0.600 0.105	0.200	0.111		0.089 0.050 0.005
Nas/Ske Stikine	200 102	0.040 0.078	0.045 0.176	0.800 0.157		0.588
	102	0.078				
Stikine	102	0.078			Tahltan	0.588
Stikine Mean Proportion C	102	0.078	0.176		Tahltan 0.147 0.005 0.680 0.137	0.588
Stikine  Mean Proportion C  4 way model:  Ak. I Ak. II Tahltan	102 orrectly C1a 190 200 200 102	0.078 assified  Ak. I 0.558 0.115 0.150 0.039	0.176  Ak. II  0.216 0.800 0.020		0.147 0.005 0.680	0.588 0.707 Stikine 0.079 0.080 0.150
Stikine  Mean Proportion C  4 way model:  Ak. I Ak. II Tahltan Stikine	102 orrectly C1a 190 200 200 102	0.078 assified  Ak. I 0.558 0.115 0.150 0.039	0.176  Ak. II  0.216 0.800 0.020		0.147 0.005 0.680	0.588 0.707 Stikine 0.079 0.080 0.150 0.657
Stikine  Mean Proportion C  4 way model:  Ak. I Ak. II Tahltan Stikine  Mean Proportion C	102 orrectly C1a 190 200 200 102	0.078 assified  Ak. I 0.558 0.115 0.150 0.039 assified	0.176  Ak. II  0.216 0.800 0.020 0.167	0.157	0.147 0.005 0.680	0.588 0.707 Stikine 0.079 0.080 0.150 0.657
Stikine  Mean Proportion C  4 way model:  Ak. I Ak. II Tahltan Stikine  Mean Proportion C  3 way model:  Ak. I Ak. I Ak. II	190 200 200 102 orrectly Cla	0.078 assified  Ak. I 0.558 0.115 0.150 0.039 assified  Ak. I 0.684 0.170 0.060	0.176  Ak. II  0.216 0.800 0.020 0.167  Ak. II  0.184 0.825	0.157 Nas/Ske 0.132 0.005	0.147 0.005 0.680	0.588 0.707 Stikine 0.079 0.080 0.150 0.657
Stikine  Mean Proportion C  4 way model:  Ak. I Ak. II Tahltan Stikine  Mean Proportion C  3 way model:  Ak. I Ak. I Ak. II Nas/Ske	190 200 200 102 orrectly Cla	0.078 assified  Ak. I 0.558 0.115 0.150 0.039 assified  Ak. I 0.684 0.170 0.060	0.176  Ak. II  0.216 0.800 0.020 0.167  Ak. II  0.184 0.825	0.157 Nas/Ske 0.132 0.005	0.147 0.005 0.680	0.588 0.707 Stikine 0.079 0.080 0.150 0.657
Stikine  Mean Proportion C  4 way model:  Ak. I Ak. II Tahltan Stikine  Mean Proportion C  3 way model:  Ak. I Ak. II Nas/Ske  Mean Proportion C	190 200 200 102 orrectly Cla	0.078 assified  Ak. I 0.558 0.115 0.150 0.039 assified  Ak. I 0.684 0.170 0.060 assified	0.176  Ak. II  0.216 0.800 0.020 0.167  Ak. II  0.184 0.825 0.065	0.157 Nas/Ske 0.132 0.005	0.147 0.005 0.680 0.137	0.588 0.707 Stikine 0.079 0.080 0.150 0.657

Appendix B.2 (p. 2 of 2)

Actual Group of Origin	Sample Size	(	Classifie	d Group o	of Origin	
3 way model :		Ak. I	Ak. II			Stikine
Ak. I Ak. II Stikine	190 200 102	0.689 0.105 0.069	0.211 0.820 0.157	,		0.100 0.075 0.775
Mean Proportion C	orrectly Cla	assified				0.761
3 way model :		Ak. I		Nas/Ske	Tahltan	
Ak. I Nas/Ske Tahltan	190 200 200	0.779 0.080 0.085		0.100 0.685 0.200	0.121 0.235 0.715	
Mean Proportion C	orrectly Cla	assified				0.726
3 way model :		Ak. I		Nas/Ske		Stikine
Ak. I Nas/Ske Stikine	190 200 102	0.784 0.065 0.118		0.089 0.825 0.176		0.126 0.110 0.706
Mean Proportion C	orrectly Cla	assified				0.772
3 way model :		Ak. I			Tahltan	Stikine
Ak. I Tahltan Stikine	190 200 102	0.742 0.105 0.137			0.153 0.815 0.176	0.105 0.080 0.686
Mean Proportion C	orrectly Cla	assified				0.748
2 way model :					Tahltan	Stikine
Tahltan Stikine	200 102				0.895 0.127	0.105 0.873
Mean Proportion C	orrectly Cl	assified				0.884

Appendix B.3. Classification matrices for linear discriminant function models used to classify age-2.2 sockeye salmon from Alaska's District 106 and 108 and Canada's Stikine River gill net fisheries, 1987.

Actual Group of Origin	Sample Size	Classified Group of Origin						
2 way model :		Ak. I	Nas/Ske					
Ak. I	135	0.919	0.081					
Nas/Ske	182	0.071	0.929					
Mean Proportion (	Correctly Cla	assified			0.924			
2 way model :			T:	ahltan	Stikine			
Tahltan	17			0.941	0.059			
Stikine	8			0.000	1.000			
Mean Proportion (	Correctly Cl	assified			0.971			

Appendix B.4. Classification matrices for linear discriminant function models used to classify age-2.3 sockeye salmon from Alaska's District 106 and 108 and Canada's Stikine River gill net fisheries, 1987.

Actual Group of Origin	Sample Size		Classifi	ed Group	of Origin	
4 way model :		Ak. I	Ak. II	Nas/Ske	Tahltan	
Ak. I Ak. II Nas/Ske Tahltan	184 173 63 100	0.587 0.243 0.016 0.070	0.299 0.734 0.048 0.000	0.092 0.012 0.762 0.170	0.022 0.012 0.175 0.760	
Mean Proportion	Correctly Cla	ssified				0.711
3 way model :		Ak. I	Ak. II	Nas/Ske		
Ak. I Ak. II Nas/Ske	184 173 63	0.630 0.277 0.048	0.304 0.711 0.048	0.092 0.012 0.905		
Mean Proportion	Correctly Cla	ssified				0.749
3 way model		Ak. I	Ak. II	·	Tahltan	
Ak. I Ak. II Tahltan	184 173 100	0.603 0.243 0.060	0.359 0.740 0.000		0.038 0.017 0.940	
Mean Proportion	Correctly Cla	ssified				0.761
2 way model :		Ak. I	Ak. II			
Ak. I Ak. II	18 <b>4</b> 173	0.701 0.225	0.299 0.775			
Mean Proportion	Correctly Cla	ssified				0.738
2 way model :		Ak. I		Nas/Ske		
Ak. I Nas/Ske	18 <b>4</b> 63	0.929		0.071 0.937		
Mean Proportion	Correctly Cla	ssified				0.933
2 way model :			Ak. II	Nas/Ske		
Ak. II Nas/Ske	173 63		0.960 0.127	0.040 0.873		
Mean Proportion	Correctly Cla	ssified				0.916
2 way model :					Tahltan	Sitkine
Tahltan Stikine	100 9				0.850 0.222	0.150 0.778
Mean Proportion	Correctly Cla	ssified				0.814

Appendix C.1. Estimated contributions of sockeye salmon stocks originating in Alaska and Canada to Alaska's Subdistrict 106-30 drift gill net fishery, 1987.

			Catch	By Age	Class				Standard	90% C	.I. a
Dates	Group	1.2	1.3	2.2	2.3	Other	Total	Percent	Error	Lower	Upper
6/21-6/27	Ak. I	83	568	81	77	0	809	62.1	153.54	556	1,062
Week 26	Ak. II	2	282	0	28	0	312	23.9	114.50	124	500
	Nas/Ske	6	0	27	0	0	33	2.5	16.10	7	59
	Tahltan	0	133	0	2	0	135	10.4	97.85	0	296
	Stikine	0	14	0	0	0	14	1.1	71.99	0	132
	Total	91	997	108	107	0	1,303				
6/28-7/04	Ak. I	177	965	183	168	18	1,511	51.8	231.88	1,130	1,892
Week 27	Ak. II	4	970	0	60	12	1,046	35.8	200.28	717	1,375
	Nas/Ske	14	279	62	0	3	358	12.3	119.67	161	555
	Tahltan	0	0	0	4	0	4	0.1	13.70	0	27
	Stikine Total	0 195	0 2,214	0 2 <b>4</b> 5	0 232	0 33	0 2,919	0.0			
			·				•				
7/05-7/11	Ak. I	498	2,710	324	556	20	4,108	73.8	418.14	3,420	4,796
Week 28	Ak. II	0	395	0	239	3	637	11.4	298.93	145	1,129
	Nas/Ske	138	470	181	12	4	805	14.5	241.55	408	1,202
	Tahltan	0	0	0	6	0	6	0.1	24.63	. 0	47
	Stikine Total	0 636	14 3,589	0 505	0 813	0 27	14 5,570	0.3	235.56	0	401
7/10 7/10		421	2 460	404				4m A			
7/12-7/18 Week 29	Ak. I Ak. II	431 6	3,468	404	1,342	69	5,714	67.0	653.38	4,639	6,789
Megs 23	Nas/Ske	195	1,100 516	0 138	0 173	14	1,120	13.1	428.12	416	1,824
	Tahltan	0	75	0	0	13	1,035 76	12.1	368.72	428 0	1,642
	Stikine	0	73 573	0	0	1 7	580	0.9 6.8	307.85	0	582 1,308
	Total	632	5,732	542	1,515	104	8,525	0.0	442.59	Ū	1,308
7/19-7/25	Ak. I	905	2,861	574	643	24	5,007	47.1	734.51	3,799	6,215
Week 30	Ak. II	0	3,379	0	1,085	22	4,486	42.2	640.08	3,433	5,539
mode 50	Nas/Ske	89	859	89	104	6	1,147	10.8	366.67	544	1,750
	Tahltan	0	0	0	0	0	0	0.0	300.07	344	1,750
	Stikine	o o	ō	Ŏ	0	ō	0	0.0			
	Total	994	7,099	663	1,832	52	10,640				
7/26-8/01	Ak. I	618	1,698	677	0	14	3,007	23.6	755.18	1,765	4,249
Week 31	Ak. II	115	4,544	0	2,583	34	7,276	57.0	712.27	6,104	8,448
	Nas/Ske	183	1,844	259	185	12	2,483	19.5	486.17	1,683	3,283
	Tahltan	0	· o	0	0	0	. 0	0.0		•	•
	Stikine	0	0	0	0	0	0	0.0			
	Total	916	8,086	936	2,768	60	12,766				
8/02-8/08	Ak. I	507	1,884	642	0	41	3,074	25.7	637.62	2,025	4,123
Week 32	Ak. II	223	3,995	0	2,881	97	7,196	60.2	587.83	6,229	8,163
	Nas/Ske	326	848	434	53	22	1,683	14.1	357.54	1,095	2,271
	Tahltan	0	0	0	0	0	0	0.0			
	Stikin <b>e</b>	0	0	0	0	0	0	0.0			
	Total	1,056	6,727	1,076	2,934	160	11,953				
8/09-9/19	Ak. I	274	1,111	308	154	11	1,858	51.8	232.35	1,476	2,240
Wks 33-38		0	427	0	718	5	1,150	32.1		833	1,467
	Nas/Ske	162	81	202	29	2	476	13.3	107.76	299	653
	Tahltan	0	0	0	0	0	0	0.0			
	Stikine Total	0 <b>436</b>	102 1,721	0 510	0 901	0 18	102 3,586	2.8	117.67	0	296
							· · · · ·				
	Ak. I Ak. II	3,493 350	15,265 15,092	3,193 0	2,940 7,594	197 187	25,088 23,223		1499.52 1274.74	22,621 21,126	27,555 25,320
Fishery	Nas/Ske	1,113	4,897	1,392	556	62	8,020	14.0		6,625	9,415
3-1	Tahltan	0	208	1,392	12	1	221	0.4	324.23	0,023	754
Total				•		_					, , ,
Total	Stikine	0	703	0	0	7	710	1.2	520.01	0	1,565

The standard errors are minimum estimates since no estimates of the variance for stocks contributing 0 fish during a given week or for the 'other' age class are available. The 90% confidence intervals are affected in like manner.

Appendix C.2. Estimated CPUE and migratory timing of sockeye salmon stocks in Alaska's Subdistrict 106-30 drift gill net fishery, 1987.

		Average		C	atch per	Boat Day		
Stat Week	Days Open	Number Boats	Ak. I	Ak. II	Nas-Ske	Tahltan	Stikine	Total
26	2	29	1.4	5	1	2	0	22
27	2	36	21	15	5	0	0	41
28	2	32	64	10	13	0	0	87
29	2	74	39	8	7	1	4	58
30	2	41	61	55	14	0	0	130
31	2	49	31	74	25	0	0	130
32	2	64	24	56	13	0	0 -	93
33-38	6	26	12	7	3	0	1	23
Total			265	230	81	3	5	584

## Migratory Timing

~. ·		Proport	ion of Ca	tch per B	oat Day	
Stat Week	Ak. I	Ak. II	Nas-Ske	Tahltan	Stikine	Total
26	0.05	0.02	0.01	0.78	0.05	0.04
27	0.08	0.06	0.06	0.02	0.00	0.07
28	0.24	0.04	0.16	0.03	0.04	0.15
29	0.15	0.03	0.09	0.17	0.78	0.10
30	0.23	0.24	0.17	0.00	0.00	0.22
31	0.12	0.32	0.31	0.00	0.00	0.22
32	0.09	0.24	0.16	0.00	0.00	0.16
33-38	0.04	0.03	0.04	0.00	0.13	0.04
Total	1.00	1.00	1.00	1.00	1.00	1.00

Appendix C.3. Estimated contributions of sockeye salmon stocks originating in Alaska and Canada to Alaska's Subdistrict 106-41 drift gill net fishery, 1987.

			Catch	By Age	Class				Standard	90%	.I. a
Dates	Group	1.2	1.3	2.2	2.3	Other	Total	Percent	a	Lower	Upper
6/21-6/27	Ak. I	305	1,896	319	312	54	2,886	75.1	222.8	2,519	3,253
Week 26	Ak. II	1	587	0	19	12	619	16.1	175.4	331	907
	Nas/Ske	0	248	0	35	6	289	7.5	119.8	92	486
	Tahltan	0	0	0	50	1	51	1.3	26.7	7	95
	Stikine Total	0 30 <b>6</b>	0	0 319	0 <b>416</b>	0 73	0 3,845	0.0			
	TOTAL	306	2,731	319	410	73	3,645				
6/28-7/04 Week 27	Ak. I	613 0	3,630 869	579 0	521 113	79 14	5,422	72.2	438.4	4,701	6,143
WGGK 27	Ak. II Nas/Ske	16	806	98	62	14	996 996	13.3 13.3	334.5 260.1	446 568	1,546 1,424
	Tahltan	0	0	0	99	1	100	1.3	54.6	10	190
	Stikine	ō	ō	ō	ō	0	0	0.0			130
	Total	629	5,305	677	795	108	7,514				
7/05-7/11	Ak. I	866	3,846	480	1,121	132	6,445	42.5	834.0	5,073	7,817
Week 28	Ak. II	0	2,665	0	225	61	2,951	19.4	610.5	1,947	3,955
	Nas/Ske	481	3,602	530	247	102	4,962	32.7	628.2	3,929	5,995
	Tahltan	0	379	0	379	16	774	5.1	447.1	39	1,509
	Stikine	0	42	0	0	1	43	0.3	506.7	0	876
	Total	1,347	10,534	1,010	1,972	312	15,175				
7/12-7/18	Ak. I	1,134	6,794	505	1,384	110	9,927	72.1	819.2	8,579	11,275
Week 29	Ak. II	221	1,632	0	213	23	2,089	15.2	642.4	1,032	3,146
	Nas/Ske	203	1,116	187	105	18	1,629	11.8	462.6	868	2,390
	Tahltan	0	0	0	115	1	116	0.8	85.4	0	256
	Stikine Total	0 1,558	0 9,542	0 692	0 1,817	0 152	0 13,761	0.0			
					-,		·				
7/19-7/25		837	4,339	844	1,120	68	7,208	51.4	865.8	5,784	8,632
Week 30	Ak. II	0	4,145	0	1,255	51	5,451	38.8	680.8	4,331	6,571
	Nas/Ske	68	860	105	0	10	1,043	7.4	398.5	387	1,699
	Tahltan Stikine	0	106 213	0	7 0	1 2	114 215	0.8 1.5	334.7 475.0	0	665 996
	Total	905	9,663	949	2,382	132	14,031	1.5	475.0	J	990
7/26-8/01	Ak. I	561	2,378	459	971	49	4,418	43.2	532.9	3,541	5,295
Week 31	Ak. II	108	3,329	0	1,082	49	4,568	44.6	766.3	3,307	5,829
	Nas/Ske	104	720	409	0	13	1,246	12.2	253.8	828	1,664
	Tahltan	0	0	0	0	0	0	0.0			•
	Stikine	0	0	0	0	0	0	0.0			
	Total	773	6,427	868	2,053	111	10,232				
8/02-8/08	Ak. I	583	2,176	490	0	57	3,306	29.9	513.0	2,462	4,150
Week 32	Ak. II	0	2,880	0	2,520	94	5,494	49.6	460.9	4,736	6,252
	Nas/Ske	253	1,232	694	57	39	2,275	20.5	328.9	. 1,734	2,816
	Tahltan	0	0	0	0	0	0	0.0			
	Stikine	0	0	0	0	0	0	0.0			
	Total	836	6,288	1,184	2,577	190	11,075				
9/09-9/19		297	1,227	241	0	39	1,804	51.1	160.3	1,540	2,068
Wks 33-38		0	155	0	821	22	998	28.3	124.2	794	1,202
	Nas/Ske	138	236	330	9	17	730	20.7	107.6	55 <b>3</b>	907
	Tahltan	0	0	0	0	0	0	0.0			
	Stikine Total	0 435	0 1,618	0 571	0 830	0 78	0 3,532	0.0			
									1711 0	20 606	44 000
	Ak. I	5,196 330	26,286	3,917 0	5,429	588 32 <b>6</b>	41,416 23,166	52.3 29.3	1711.9 1444.9	38,600 20,789	44,232 25,543
Fishery	Ak. II Nas/Ske	1,263	16,262 8,820	2,353	6,248 51 <b>5</b>	219	13,170	29.3 16.6		11,497	14,843
_	Nas/Ske Tahltan	1,263	485	2,353	650	219	1,155	1.5	568.2	220	2,090
Total		-				~ ~	-,	1.5			_, -, -, -
Total	Stikine	0	255	0	0	3	258	0.3	694.5	0	1,400

The standard errors are minimum estimates since no estimates of the variance for stocks contributing 0 fish during a given week or for the 'other' age class are available. The 90% confidence intervals are affected in like manner.

Appendix C.4. Estimated CPUE and migratory timing of sockeye salmon stocks in Alaska's Subdistrict 106-41 drift gill net fishery, 1987.

CPUE								
Stat	Days	Average Number		C	atch per	Boat Day		
Week	Open	Boats	Ak. I	Ak. II	Nas-Ske	Tahltan	Stikine	Total
26	2	66	22	5	2	0	0	29
27	2	72	38	7	7	1	0	52
28	2	73	44	20	34	5	0	104
29	2	82	61	13	10	1	0	84
30	2	45	80	61	12	1	2	156
31	2	48	46	48	13	0	0.	107
32	2	48	34	57	24	0	0	115
33-38	5.5	19	17	9	7	0	0	33
Total			342	219	108	8	3	680

## Migratory Timing

		Proport	ion of Ca	tch per B	oat Day	
Stat Week	Ak. I	Ak. II	Nas-Ske	Tahltan	Stikine	Total
26	0.06	0.02	0.02	0.05	0.00	0.04
27	0.11	0.03	0.06	0.08	0.00	0.08
28	0.13	0.09	0.31	0.63	0.11	0.15
29	0.18	0.06	0.09	0.08	0.00	0.12
30	0.23	0.28	0.11	0.15	0.89	0.23
31	0.13	0.22	0.12	0.00	0.00	0.16
32	0.10	0.26	0.22	0.00	0.00	0.17
33-38	0.05	0.04	0.06	0.00	0.00	0.05
Total	1.00	1.00	1.00	1.00	1.00	1.00

Appendix C.5. Estimated contributions of sockeye salmon stocks originating in Alaska and Canada to Alaska's District 108 drift gill net fishery, 1987.

				Catch					
Dates	Group	1.2	1.3	2.2	2.3	0.	Other	Total	Percent
6/21-6/27									
Week 26	Total							189	
6/28-7/04									
Week 27	Total							245	
7/05-7/11									
Week 28	Total							759	
7/12-7/18	Ak. I		37			0		37	8.8
Week 29	Ak. II		14			0		14	3.3
	Nas/Ske		0			0		0	0.0
	Tahltan		126			0		126	30.5
	Stikine		112			10		122	27.0
	Total	62	289	21	41	10	0	423	
7/19-8/22	No	fishery	openings						
Wks 30-34									
8/23-8/29									
Week 35	Total							2	
8/30-9/05									
Week 36	Total							1	
9/06-9/12									
Week 37	Total							1	
	Ak. I		37				0	37	2.3
	Ak. II		14				0	14	0.9
	Nas/Ske		0				0	0	0.0
Fishery	Tahltan		126				0	126	7.8
Total	Stikine		112				0	112	6.9
	Total		289				0	289	17.9
	Unknown	62		21	41			124	7.7
	Unsampled							1197	74.4
	Grand Tota	al						1610	

 $<sup>^{\</sup>mathrm{a}}$  Samples available from statistical week 29 only.

Appendix D.1. Estimated contributions of sockeye salmon stock groups to Alaska's District 106 drift gill net fisheries (1982-1987).

		<del></del>	Year and	Date of	Stat. Week	25 (June	<del>=</del> )
Stat. Week	Group	1982 13-19	1983 12-18	1984 17-23		1986 15-21	1987 14 <b>-</b> 20
25 b	Alaska Nas-Ske Tahltan Stikine Total	c 4,126 2,897 129 7,152	not open	1,364 201 112 8 1,685	1,477 1,444 3	2,212 351 0 0 2,563	not open
26	Alaska Nas-Ske Tahltan Stikine Total	18,625 11,806 6,540 36,971	3,155 1,587 507 104 5,353	2,671 562 280 180 3,693	1,789 1,365 170	3,064 503 62 0 3,629	4,626 322 186 14 5,148
27	Alaska Nas-Ske Tahltan Stikine Total	25,978 13,240 5,932 45,150	4,037 1,647 1,327 51 7,062	5,475 1,078 844 312 7,709	6,003 7,801 270	12,124 3,050 1,184 420 16,778	8,975 1,354 104 0 10,433
28	Alaska Nas-Ske Tahltan Stikine Total	15,318 12,197 9,900 37,415	4,389 913 736 44 6,082	6,884 2,563 1,134 50 10,631	13,132 6,288 492	not open	14,141 5,767 780 57 20,745
29	Alaska Nas-Ske Tahltan Stikine Total	9,110 4,108 4,686 17,904	3,411 250 355 240 4,256	13,314 3,135 307 2,420 19,176	15,424 7,152 299	6,086 424 2 0 6,512	18,850 2,664 192 580 22,286
30	Alaska Nas-Ske Tahltan Stikine Total	15,781 10,975 7,990 34,746	9,251 1,451 1,626 65 12,393	15,035 6,937 0 416 22,388	24,173 0 1,305	10,708 4,039 0 64 14,811	22,152 2,190 114 215 24,671
31 <sup>d</sup>	Alaska Nas-Ske Tahltan Stikine Total	5,249 6,573 2,458 14,280	4,599 3,227 136 0 7,962	8,388 6,654 0 401 15,443	30,943 0 0	12,959 7,553 712 16 21,240	19,269 3,729 0 0 22,998
32	Alaska Nas-Ske Tahltan Stikine Total		883 357 129 36 1,405	4,042 1,631 0 97 5,770	5,602 0 46	9,296 7,612 0 105 17,013	19,070 3,958 0 0 23,028
33	Alaska Nas-Ske Tahltan Stikine Total		1,561 762 133 74 2,530	1,812 1,080 0 120 3,012	0 182	5,397 10,182 121 0 15,700	5,810 1,206 0 102 7,118
34	Alaska Nas-Ske Tahltan Stikine Total		790 143 51 2 986	1,382 820 0 80 2,282	3,560 4,702 0 196 8,458	3,293 8,970 0 1 12,264	
35-40	Alaska Nas-Ske Tahltan Stikine Total		595 274 30 16 915				
	Alaska Nas-Ske Tahltan Stikine Total	94,187 61,796 37,635 193,618	32,671 10,611 5,030 632 48,944	60,367 24,661 2,677 4,084 91,789	126,952 110,504 24,050 2,963 264,469	65,139 42,684 2,081 606 110,510	112,893 21,190 1,376 968 136,427

a 106-30 was open but 106-41 was not during weeks 25-28 in 1984, week 26 in 1985, and week 29 in 1986.
Ak. I and II standards (1986 and 1987) were combined to facilitate comparision with the historical analyses.
Tahltan and Stikine (non-Tahltan) were not separated in the 1982 analysis.
The last figures in each column include catch from that week through the end of the season.

Appendix D.2. Estimated contribution rates of sockeye salmon stock groups to Alaska's District 106 drift gill net fisheries (1982-1987).

			Year and	Date of	Stat. Week	25 (June)	·
Stat. Week	Group	1982 13-19	1983 12-18	1984 17-23		1986 15-21	1987 14-20
25 b	Alaska Nas-Ske Tahltan	0.577 0.405	not open	0.809 0.119 0.066	0.121 0.118	0.863 0.137 0.000	not open
26	Stikine Alaska Nas-Ske Tahltan Stikine	0.018 0.504 0.319 0.177	0.589 0.296 0.095 0.019	0.005 0.723 0.152 0.076 0.049	0.675 0.175 0.133	0.000 0.844 0.139 0.017 0.000	0.899 0.063 0.036 0.003
27	Alaska Nas-Ske Tahltan Stikine	0.575 0.293 0.131	0.572 0.233 0.188 0.007	0.710 0.140 0.109 0.040	0.211	0.723 0.182 0.071 0.025	0.860 0.130 0.010 0.000
28	Alaska Nas-Ske Tahltan Stikine	0.409 0.326 0.265	0.722 0.150 0.121 0.007	0.648 0.241 0.107 0.005	0.349	not open	0.682 0.278 0.038 0.003
29	Alaska Nas-Ske Tahltan Stikine	0.509 0.229 0.262	0.801 0.059 0.083 0.056	0.694 0.163 0.016 0.126	0.351 0.163	0.935 0.065 0.000 0.000	0.846 0.120 0.009 0.026
30	Alaska Nas-Ske Tahltan Stikine	0.454 0.316 0.230	0.746 0.117 0.131 0.005	0.672 0.310 0.000 0.019	0.515	0.723 0.273 0.000 0.004	0.898 0.089 0.005 0.009
31 d	Alaska Nas-Ske Tahltan Stikine	0.368 0.460 0.000 0.172	0.578 0.405 0.017 0.000	0.543 0.431 0.000 0.026	0.613	0.610 0.356 0.034 0.001	0.838 0.162 0.000 0.000
32	Alaska Nas-Ske Tahltan Stikine		0.628 0.254 0.092 0.026	0.701 0.283 0.000 0.017	0.414	0.546 0.447 0.000 0.006	0.828 0.172 0.000 0.000
33	Alaska Nas-Ske Tahltan Stikine		0.617 0.301 0.053 0.029	0.602 0.359 0.000 0.040	0.570	0.344 0.649 0.008 0.000	0.816 0.169 0.000 0.014
34	Alaska Nas-Ske Tahltan Stikine		0.801 0.145 0.052 0.002	0.606 0.359 0.000	0.556 0.000	0.269 0.731 0.000 0.000	
35-40	Alaska Nas-Ske Tahltan Stikine		0.650 0.299 0.033 0.017				
	Alaska Nas-Ske Tahltan Stikine	0.486 0.319 0.000 0.194	0.668 0.217 0.103 0.013	0.658 0.269 0.029	0.418	0.589 0.386 0.019 0.005	0.827 0.155 0.010 0.007

a 106-30 was open but 106-41 was not during weeks 25-28 in 1984, week 26 in 1985, and week 29 in 1986.

Ak. I and II standards (1986 and 1987) were combined to facilitate comparison with the historical analyses.

Tahltan and Stikine (non-Tahltan) were not separated in the 1982

d analysis. The last figures in each column include catch from that week through the end of the season.

Appendix D.3. Estimated contributions of sockeye salmon stock groups to Alaska's Subdistricts 106-30 and 106-41 drift gill net fisheries (1985-1987).

		106-30	Year and	i Date	106-41	Year and	d Date
Stat. Week	Group	1985 16-22	1986 15-21	1987 14-20	1985 16-22	1986 15 <b>-</b> 21	198 14-20
25 <sup>a</sup>	Ak. I Ak. II Nas-Ske Tahltan Stikine Total	1,821 285 451 3 2,560	553 27 64 0 0	not open	7,458 1,192 993 0 9,643	1,659 0 287 0 0 1,946	not oper
26	Ak. I Ak. II Nas-Ske Tahltan Stikine Total	6,909 1,789 1,365 170 10,233	537 46 59 0 0	809 312 33 135 14 1,303	not open	2,527 14 444 62 0 3,047	2,88 61 28 5
27	Ak. I Ak. II Nas-Ske Tahltan Stikine Total	4,879 2,099 558 0 7,536	3,539 74 673 9 0 4,295	1,511 1,046 358 4 0 2,919	9,435 3,904 7,243 270 20,852	8,585 536 2,377 1,175 420 13,093	5,42 99 99 10 7,51
28	Ak. I Ak. II Nas-Ske Tahltan Stikine Total	5,985 5,165 19 361 11,530	not open	4,108 637 805 6 14 5,570	11,704 7,967 6,269 131 26,071	not op <b>en</b>	6,44 2,95 4,96 77 4 15,17
29	Ak. I Ak. II Nas-Ske Tahltan Stikine Total	3,642 4,067 2,856 17 10,582	6,086 1,115 424 2 0 7,627	5,714 1,120 1,035 76 580 8,525	17,383 11,357 4,296 282 33,318	not op <b>en</b>	9,92 2,08 1,62 11
30	Ak. I Ak. II Nas-Ske Tahltan Stikine Total	7,544 11,215 0 502 19,261	5,400 2,092 1,295 0 0 8,787	5,007 4,486 1,147 0 0	13,947 12,958 0 803 27,708	5,308 4,553 2,744 0 64 12,669	7,20 5,45 1,04 11 21 14,03
31	Ak. I Ak. II Nas-Ske Tahltan Stikine Total	6,349 10,626 0 0 16,975	5,590 5,756 2,993 0 0 14,339	3,007 7,276 2,483 0 0	13,158 20,317 0 0 33,475	7,369 6,589 4,560 712 16 19,246	4,41 4,56 1,24
32	Ak. I Ak. II Nas-Ske Tahltan Stikine Total	2,730 1,109 0 46 3,885	3,659 3,350 2,931 0 105 10,045	3,074 7,196 1,683 0 0	5,161 4,493 0 0 9,654	5,637 4,456 4,681 0 0	3,30 5,49 2,27
33 b	Ak. I Ak. II Nas-Ske Tahltan Stikine Total	2,640 2,582 0 72 5,294	2,042 1,058 2,696 0 0 5,796	1,858 1,150 476 0 102 3,586	2,647 4,677 0 110 7,434	3,355 3,104 7,486 121 0	1,80 99 73
34	Ak. I Ak. II Nas-Ske Tahltan Stikine Total	1,890 3,152 0 81 5,123	1,732 1,219 5,336 0 0 8,287		1,207 1,550 0 115 2,872	1,095 926 2,906 0 4,927	
35-40	Ak. I Ak. II Nas-Ske Tahltan Stikine Total				463 547 0 51 1,061	466 280 728 0 1 1,475	
otals	Ak. I Ak. II Nas-Ske Tahltan Stikine Total	44,389 42,089 5,249 1,252 92,979	29,138 14,737 16,471 11 105 60,462	25,088 23,223 8,020 221 710 57,262	82,563 68,962 18,801 1,762 172,088	36,001 20,458 26,213 2,070 501 85,243	41,41 23,16 13,17 1,15 25 79,16

 $_{
m b}^{
m a}$  Ak. I and Ak. II stocks were not analyzed separately in 1985. The last figures in each column include catch from that week through the end of the season.

Appendix D.4. Estimated contribution rates of sockeye salmon stock groups to Alaska's Subdistricts 106-30 and 106-41 drift gill net fisheries (1985-1987).

		106-30	Year and	Date	106-41	Year and	Date
Stat. Week	Group	1985 16-22	1986 15-21	1987 14-20	1985 16-22	1986 15-21	1987 14-20
25 a	Ak. I Ak. II Nas-Ske Tahltan Stikine	0.711 0.111 0.176 0.001	0.859 0.042 0.099 0.000 0.000	not open	0.773 0.124 0.103 0.000	0.853 0.000 0.147 0.000 0.000	not open
26	Ak. I Ak. II Nas-Ske Tahltan Stikine	0.675 0.175 0.133 0.017	0.836 0.072 0.092 0.000 0.000	0.621 0.239 0.025 0.104 0.011	not open	0.829 0.005 0.146 0.020 0.000	0.751 0.161 0.075 0.013 0.000
27	Ak. I Ak. II Nas-Ske Tahltan Stikine	0.647 0.279 0.074 0.000	0.824 0.017 0.157 0.002 0.000	0.518 0.358 0.123 0.001 0.000	0.452 0.187 0.347 0.013	0.656 0.041 0.182 0.090 0.032	0.722 0.133 0.133 0.013 0.000
28	Ak. I Ak. II Nas-Ske Tahltan Stikine	0.519 0.448 0.002 0.031	not open	0.738 0.114 0.145 0.001 0.003	0.449 0.306 0.240 0.005	not open	0.425 0.194 0.327 0.051 0.003
29	Ak. I Ak. II Nas-Ske Tahltan Stikine	0.344 0.384 0.270 0.002	0.798 0.146 0.056 0.000 0.000	0.670 0.131 0.121 0.009 0.068	0.522 0.341 0.129 0.008	not open	0.721 0.152 0.118 0.008 0.000
30	Ak. I Ak. II Nas-Ske Tahltan Stikine	0.392 0.582 0.000 0.026	0.615 0.238 0.147 0.000 0.000	0.471 0.422 0.108 0.000 0.000	0.503 0.468 0.000 0.029	0.419 0.359 0.217 0.000 0.005	0.514 0.388 0.074 0.008 0.015
31	Ak. I Ak. II Nas-Ske Tahltan Stikine	0.374 0.626 0.000 0.000	0.390 0.401 0.209 0.000 0.000	0.236 0.570 0.195 0.000 0.000	0.393 0.607 0.000 0.000	0.383 0.342 0.237 0.037 0.001	0.432 0.446 0.122 0.000 0.000
32	Ak. I Ak. II Nas-Ske Tahltan Stikine	0.703 0.285 0.000 0.012	0.364 0.333 0.292 0.000 0.010	0.257 0.602 0.141 0.000 0.000	0.535 0.465 0.000 0.000	0.382 0.302 0.317 0.000 0.000	0.299 0.496 0.205 0.000
33	Ak. I Ak. II Nas-Ske Tahltan Stikine	0.499 0.488 0.000 0.014	0.352 0.183 0.465 0.000 0.000	0.518 0.321 0.133 0.000 0.028	0.356 0.629 0.000 0.015	0.239 0.221 0.532 0.009 0.000	0.511 0.283 0.207 0.000 0.000
34 b	Ak. I Ak. II Nas-Ske Tahltan Stikine	0.369 0.615 0.000 0.016	0.209 0.147 0.644 0.000 0.000		0.420 0.540 0.000 0.040	0.222 0.188 0.590 0.000	
35-40	Ak. I Ak. II Nas-Ske Tahltan Stikine				0.436 0.516 0.000 0.048	0.316 0.190 0.494 0.000 0.001	
Totals	Ak. I Ak. II Nas-Ske Tahltan Stikine	0.477 0.453 0.056 0.013	0.482 0.244 0.272 0.000 0.002	0.438 0.406 0.140 0.004 0.012	0.480 0.401 0.109 0.010	0.422 0.240 0.308 0.024 0.006	0.523 0.293 0.166 0.015 0.003

<sup>&</sup>lt;sup>a</sup> Ak. I and Ak. II stocks were not analyzed separately in 1985. The last figures in each column include catch from that week through the end of the season.

Appendix D.5. Estimated contributions of sockeye salmon stock groups to Alaska's District 108 drift gill net fisheries, 1986-1987.

0	Object:	Cato	:h	Propos	tions
Stat. Week	Stock Group	1986	1987	1986	1987
25	Alaska I Alaska II Nas/Ske Tahltan Stikine Total	2 4 1 5 18 30		0.067 0.133 0.033 0.167 0.600	
26 <sup>a</sup>	Alaska I Alaska II Nas/Ske Tahltan Stikine Sti. Comb. Non-Sti. Total	1 2 0 3 8	160 29 189	0.071 0.143 0.000 0.214 0.571	0.849 0.151
27	Sti. Comb. Non-Sti. Total	••	219 26 245	-	0.89 <b>4</b> 0.106
28	Sti. Comb. Non-Sti. Total		684 75 759		0.901 0.099
29	Alaska I Alaska II Nas/Ske Tahltan Stikine Unknown Total		37 14 0 126 122 124 423		0.087 0.033 0.000 0.298 0.288 0.293
30	Alaska I Alaska II Nas/Ske Tahltan Stikine Total	130 298 47 346 1188 2009		0.065 0.148 0.023 0.172 0.591	
31	Alaska I Alaska II Nas/Ske Tahltan Stikine Total	20 65 5 38 555 683		0.029 0.095 0.007 0.056 0.813	
32	Alaska I Alaska II Nas/Ske Tahltan Stikine Total	13 173 9 0 593 788		0.016 0.219 0.012 0.000 0.753	
33	Alaska I Alaska II Nas/Ske Tahltan Stikine Total	7 99 5 0 340 451		0.016 0.220 0.011 0.000 0.754	
34-39	Alaska I Alaska II Nas/Ske Tahltan Stikine b Unknown Total	3 46 3 0 160	4	0.014 0.217 0.014 0.000 0.755	1.000
	Alaska I Alaska II Nas/Ske Tahltan Stikine Stik. comb. Non-Sti. Unknown	176 687 70 392 2862	37 14 0 126 122 1063 130 128 1620	0.042 0.164 0.017 0.094 0.684	0.023 0.009 0.006 0.075 0.075 0.656 0.086

a 1987 catch in weeks 26-28 estimated for total Stikine River fish (Tahltan and non-Tahltan Stikine) by averaging the weekly proportions of Stikine River fish in the commercial and test fishery catches in 1985 and 1986.

The unknown group is comprised of age classes not digitized in week 29 and fish not sampled in weeks 34-39 in 1987.

Appendix D.6. Estimated contributions of sockeye salmon stock groups to Alaska's District 108 drift gill net test fisheries, 1985-1986.

C+ -+	C+1-	Cato	ch	Propor	tions
Stat. Week	Stock Group	1985	1986	1985	1986
25	Alaska I <sup>a</sup>	22		0.198	
	Alaska II				
	Nas-Ske	0		0.000	
	Tahltan	72		0.649	
	Stikine	17		0.153	
	Total	111			
26	Alaska I	15	14	0.134	0.124
	Alaska II		0		0.000
	Nas-Ske	0	5	0.000	0.044
	Tahltan	43	81	0.384	0.717
	Stikine	54	13	0.482	0.115
	Total	112	113		
27	Alaska I	10	16	0.036	0.123
	Alaska II		0		0.000
	Nas-Ske	0	7	0.000	0.054
	Tahltan	94	95	0.335	0.731
	Stikine	177	12	0.630	0.092
	Total	281	130		
28	Alaska I	0	7	0.000	0.056
	Alaska II		12		0.095
	Nas-Ske	0	6	0.000	0.048
	Tahltan	60	79	0.213	0.627
	Stikine	222	22	0.787	0.175
	Total	282	126		
29	Alaska I	17	16	0.078	0.076
	Alaska II		13		0.062
	Nas-Ske	0	11	0.000	0.052
	Tahltan	24	60	0.110	0.286
	Stikine	178	110	0.813	0.524
	Total	219	210		
30	Alaska I		0		0.000
	Alaska II		10		0.132
	Nas-Ske		0		0.000
	Tahltan		3		0.039
	Stikine		63		0.829
	Total		76		0.023
	Alaska I	64	53	0.064	0.081
	Alaska II	• •	35	2.00.	0.053
Total	Nas-Ske	0	29	0.000	0.044
	Tahltan	293	318	0.292	0.485
	Stikine	648	220	0.645	0.336
	Total	1005	655	0.043	0.556

<sup>&</sup>lt;sup>a</sup> The Ak. I and II standards were not separated in 1985.

Appendix E.1. Estimated contribution of sockeye salmon stocks of Tahltan and non-Tahltan origin to Canada's Stikine inriver commercial fishery, 1987.

			Ca	tch by ag	e class						90%	c.I.
Dates	Group	1.2	1.3	2.2	2.3	0.	Other	Total	Percent	Standard b Error	Lower	Upper
6/28-7/04	Tahltan	2	114	3	14	0	0	133	74.3	15.3	108	158
Week 27	non-Tahltan	9	28	1	4	4	0	46	25.7	15.3	21	71
	Total	11	142	4	18	4	0	179				
7/05-7/11	Tahltan	3	138	4	3	0	0	148	87.6	12.6	127	169
Week 28	non-Tahltan	16	0	2	1	2	0	21	12.4	12.6	0	42
	Total	19	138	6	4	2	0	169				
7/12-7/18	Tahltan	33	489	16	76	0	1	615	66.4	35.0	557	673
Week 29	non-Tahltan	56	171	10	26	47	1	311	33.6	35.0	253	369
	Total	89	660	26	102	47	2	926				
7/19-7/25	Tahltan	17	188	19	38	0	2	264	24.4	43.8	192	336
Week 30	non-Tahltan	140	432	32	76	130	10	820	75.6	43.9	748	892
	Total	157	620	51	114	130	12	1,084				
7/26-8/01	Tahltan	0	47	3	0	0	0	50	11.3	23.3	12	88
Week 31	non-Tahltan	83	179	21	47	55	6	391	88.7	23.5	352	430
	Total	83	226	24	47	55	6	441				
8/02-8/08	Tahltan	98	6	3	18	0	0	125	5.1	108.9	0	304
Week 32	non-Tahltan	433	1483	19	100	280	12	2,327	94.9	109.1	2,148	2,506
	Total	531	1489	22	118	280	12	2,452				
8/09-8/15	Tahltan	15	0	6	1	o	0	22	4.0	25.1	0	63
Week 33	non-Tahltan	97	329	7	25	61	8	527	96.0	25.3	485	569
	Total	112	329	13	26	61	8	549				
8/16-8/22	Tahltan	10	3	3	0	0	0	16	6.5	15.9	0	42
Week 34	non-Tahltan	42	143	4	. 4	30	9	232	93.5	16.5	205	259
	Total	52	146	7	4	30	9	248				
8/23-9/19	Tahltan	3	2	2	0	0	0	7	7.8	14.6	0	31
Wks 35-39	non-Tahltan	14	50	2	2	14	1	83	92.2	14.7	59	107
	Total	17	52	4	2	14	1	90				
Fishery	Tahltan	181	987	59	150	0	3	1,380	22.5	129.6	1,167	1,593
Totals	non-Tahltan	890	2,815	98	285	623	47	4,758	77.5	130.0	4,544	4,972
	Total	1,071	3,802	157	435	623	50	6,138				

a Weekly catch from the Canadian Department of Fisheries and Oceans, Whitehorse, Yukon.

The standard errors are minimum estimates since no estimates of the variance for stocks contributing 0 fish to an age-group during a given week or for the 'other' age class are available. The 90% confidence intervals are affected in like manner.

Appendix E.2. Estimated CPUE and migratory timing of the Tahltan and non-Tahltan stockeye salmon stock groups in Canada's Stikine River commercial fishery, 1987.

				_	Catch per Fishing Day by Stock Group			
Stat. Week	Fishing Effort	Days	Fishing Days	Tahltan	non- Tahltan	Total		
27	15	1	15	9	3	12		
28	15	1	15	10	1	11		
29	17	1	17	36	18	54		
30	17	1	17	16	48	64		
31	17	1	17	3	23	26		
32	17	2	34	4	68	72		
3 <b>3</b>	17	1	17	1	31	32		
34	14	1	14	1	17	18		
35-39	67	2	144	0	1	1		
Totals				80	211	290		

## Migratory Timing Estimates

	Propor	tions	Migratory Timing - Cato Adjusted by Test Index				
Stat. Week	Tahltan	non- Tahltan	Index	Tahltan	non- Tahltan		
27	0.743	0.257	0.033	0.025	0.009		
28	0.876	0.124	0.143	0.125	0.018		
29	0.664	0.336	0.179	0.119	0.060		
30	0.244	0.756	0.255	0.062	0.193		
31	0.113	0.887	0.176	0.020	0.156		
32	0.051	0.949	0.116	0.006	0.111		
33	0.040	0.960	0.079	0.003	0.076		
34	0.065	0.935	0.015	0.001	0.014		
35-39	0.078	0.922	0.003	0.000	0.002		
Totals	2.873	6.127	1.000	0.361	0.639		

Weekly catch and effort data from the Canadian Department of Fisheries and Oceans, Whitehorse, Yukon.

Appendix E.3. Estimated contribution of sockeye salmon stocks of Tahltan and non-Tahltan origin to the Stikine River test fishery, 1987.

			Ca	tch by ag	e class						90%	c.I. b
Dates	Group	1.2	1.3	2.2	2.3	0,	Other	Total a	Percent	Standard b Error	Lower	Upper
6/21-7/04	Tahltan	0	50	1	1	0	0	52	86.7	3.9	46	58
Wks 26-27	non-Tahltan	1	3	0	1	3	0	8	13.3	3.9	2	14
	Total	1	53	1	2	3	0	60				
7/05-7/11	Tahltan	2	148	1	11	0	0	162	77.5	10.5	145	179
Week 28	non-Tahltan	3	28	0	11	5	0	47	22.5	10.5	30	64
	Total	5	176	1	22	5	0	209				
7/12-7/18	Tahltan	5	131	4	24	0	2	166	57.6	14.1	143	189
Week 29	non-Tahltan	10	74	3	13	21	1	122	42.4	14.1	99	145
	Total	15	205	7	37	21	3	288				
7/1 <b>9-</b> 7/25	Tahltan	4	65	5	8	0	0	82	28.0	13.8	59	105
Week 30	non-Tahltan	20	135	3	16	36	1	211	72.0	13.8	188	234
	Total	24	200	8	24	36	1	293				
7/26-8/01	Tahltan	2	20	2	1	0	0	25	8.8	8.5	11	39
Week 31	non-Tahltan	24	167	4	21	39	3	258	91.2	8.6	244	272
	Total	26	187	6	22	39	3	283				
8/02-8/08	Tahltan	2	22	0	0	0	1	25	9.3	13.1	3	47
Week 32	non-Tahltan	34	159	1	15	30	5	244	90.7	13.3	222	266
	Total	36	181	1	15	30	6	269				
8/09-8/15	Tahltan	0	0	1	0	0	0	1	0.6	10.7	0	19
Week 33	non-Tahltan	19	105	1	13	18	6	162	99.4	10.9	144	180
	Total	19	105	2	13	18	6	163				
8/16-9/12	Tahltan	0	0	0	0	0	0	0	0.0	15.1	0	25
Wks 34-37	non-Tahltan	12	59	1	8	13	9	102	100.0	15.4	77	127
	Total	12	59	1	8	13	9	102	_			
Fishery	Tahltan	15	436	14	45	0	3	513	30.8	31.0	462	564
Totals	non-Tahltan	123	730	13	98	165	25	1,154	69.2	31.4	1,102	1,206
	Total	138	1,166	27	143	165	28	1,667				

a Weekly catch from the Canadian Department of Fisheries and Oceans, Whitehorse, Yukon.

The standard errors are minimum estimates since no estimates of the variance for stocks contributing 0 fish to an age-group during a given week or for the 'other' age class are available. The 90% confidence intervals are affected in like manner.

Appendix E.4. Relative run strength and migratory timing of the Tahltan and non-Tahltan sockeye salmon in the Stikine River test fishery, 1987.

			Catch b	Stock	Group	
Stat. Week	Drifts	Actual	Adjusted	Prop.	Tahltan	non- Tahltan
26	60	8	8	0.020	0.867	0.133
27	60	5	5	0.013	0.867	0.133
28	60	56	56	0.143	0.775	0.225
29	60	70	70	0.179	0.576	0.424
30	60	100	100	0.255	0.280	0.720
31	60	69	69	0.176	0.088	0.912
32	50	38	46	0.116	0.093	0.907
33	60	31	31	0.079	0.006	0.994
34	60	6	6	0.015	0.000	1.000
35	60	1	1	0.003	0.000	1.000
Totals		384	392	1.000		

## Migratory Timing Estimates

	Proport In-rive		Migratory timing
Stat. Week	Tahltan	non- Tahltan	non- Tahltan Tahltan Total
26	0.018	0.003	0.052 0.004 0.020
27	0.011	0.002	0.032 0.003 0.013
28	0.111	0.032	0.325 0.049 0.143
29	0.103	0.076	0.302 0.115 0.179
30	0.071	0.184	0.210 0.279 0.255
31	0.016	0.161	0.046 0.244 0.176
32	0.011	0.106	0.032 0.160 0.116
33	0.000	0.079	0.001 0.119 0.079
34	0.000	0.015	0.000 0.023 0.015
35	0.000	0.003	0.000 0.004 0.003
Totals	0.341	0.659	1.000 1.000 1.000

Weekly catch and effort data from the Canadian Department of Fisheries and Oceans, Whitehorse, Yukon.

b Catch in statistical week 32 adjusted from 50 to 60 drifts.

Appendix F.1. In-season initial and adjusted stock composition estimates for sockeye salmon harvested in Alaska's Subdistrict 106-30 drift gill net fishery, 1987.

	Stat	Ini	tial Esti	mate	Adju	sted Esti	mate
Date	Stat. Week	1.2	1.3	2.3	1.2	1.3	2.3
Alaska I							
6/21-6/27 6/28-7/04 7/05-7/11 7/12-7/18 7/19-7/25 7/26-8/01 8/02-8/08	27 28 29 3 30 31	0.566 0.484 0.500 0.562 0.700 0.267	0.533 0.520 0.620 0.550 0.535 0.253 0.390	0.290 0.290 0.215 0.442 0.346 0.494	0.761 0.838 0.693 0.938 0.996 0.595	0.849 0.759 0.849 0.701 0.804 0.346	0.690 0.718 0.717 0.799 0.722 0.575
Alaska II		_					
6/21-6/27 6/28-7/04 7/05-7/11 7/12-7/18 7/19-7/25 7/26-8/01 8/02-8/08	27 28 29 3 30 31	0.174 0.129 0.211 0.104 0.150 0.167	0.258 0.280 0.150 0.190 0.273 0.448 0.400	0.548 0.526 0.544 0.407 0.423 0.394	0.188 0.000 0.120 0.000 0.000 0.405	0.124 0.177 0.062 0.130 0.029 0.461 0.555	0.310 0.282 0.268 0.201 0.278 0.425
Nass/Skee	ena	_					
6/21-6/27 6/28-7/04 7/05-7/11 7/12-7/18 7/19-7/25 7/26-8/01 8/02-8/08	27 28 29 3 29 3 30	0.043 0.242 0.184 0.167 0.150 0.200	0.032 0.080 0.160 0.160 0.101 0.184 0.100	0.065 0.039 0.101 0.035 0.058 0.042	0.000 0.162 0.156 0.062 0.004 0.000	0.024 0.028 0.089 0.169 0.081 0.193 0.078	0.000 0.000 0.000 0.000 0.000
Tahltan b	)						
6/21-6/27 6/28-7/04 7/05-7/11 7/12-7/18 7/19-7/25 7/26-8/01 8/02-8/08	27 28 3 29 5 30 31		0.129 0.040 0.030 0.080 0.061 0.069 0.060	0.032 0.053 0.013 0.023 0.000		0.003 0.000 0.000 0.000 0.000 0.000	0.000 0.000 0.000 0.000 0.000
Stikine		_					
6/21-6/27 6/28-7/04 7/05-7/11 7/12-7/18 7/19-7/25 7/26-8/01 8/02-8/08	27 28 3 29 5 30 31	0.217 0.145 0.105 0.167 0.000 0.366	0.048 0.080 0.040 0.020 0.030 0.046 0.050	0.065 0.092 0.127 0.093 0.173 0.070	0.051 0.000 0.031 0.000 0.000	0.000 0.036 0.000 0.000 0.086 0.000	0.000 0.000 0.015 0.000 0.000

Age-2.2 sockeye salmon were not analyzed in-season.

The number of age-1.2 fish sampled from the 1986 Tahltan escapement was insufficient to build a standard, thus the in-season models in 1987 did not include age-1.2 Tahltan fish.

Appendix F.2. Postseason initial and adjusted stock composition estimates for sockeye salmon harvested in Alaska's Subdistrict 106-30 drift gill net fishery, 1987.

	<b></b>		Initial E	Estimate		A	djusted E	stimate	
Date	Stat. Week	1.2	1.3	2.2 a	2.3	1.2	1.3	2.2 a	2.3
Alaska I									
6/21-6/27	26	0.693	0.468	0.703	0.525	0.908	0.570	0.745	0.724
6/28-7/04	27	0.693	0.320	0.703	0.525	0.908	0.436	0.745	0.724
7/05-7/11	28	0.629	0.460	0.615	0.474	0.783	0.755	0.642	0.684
7/12-7/18	29	0.532	0.370	0.703	0.580	0.681	0.605	0.745	0.88
7/19-7/25	30	0.691	0.293	0.806	0.265	0.910	0.403	0.866	0.35
7/26-8/01 3/02-8/08	31 32	0.536 0.408	0.276 0.230	0.68 <b>4</b> 0.577	0.220 0.212	0.674 0.480	0.210 0.280	0.723 0.597	0.00
3/02-3/08	33	0.464	0.400	0.582	0.350	0.629	0.646	0.603	0.17
Alaska II									
6/21-6/27	26	0.192	0.290		0.400	0.022	0.283		0.25
6/28-7/04	27	0.192	0.480		0.400	0.022	0.438		0.25
7/05-7/11 7/12-7/18	28 29	0.113 0.170	0.280 0.270		0.421	0.000	0.110		0.29
7/12-7/18 7/19-7/25	30	0.170	0.270		0.230 0.633	0.010 0.000	0.192 0.476		0.00
7/26-8/01	31	0.244	0.414		0.033	0.126	0.562		0.93
3/02-8/08		0.286	0.560		0.718	0.211	0.594		0.98
3/09-8/15	33	0.099	0.320		0.600	0.000	0.248		0.79
Nass/Skee	na								
6/21-6/27	26	0.115	0.048	0.297	0.050	0.070	0.000	0.255	0.000
6/28-7/04	27	0.115	0.120	0.297	0.050	0.070	0.126	0.255	0.000
7/05-7/11	28	0.258	0.160	0.385	0.079	0.217	0.131	0.358	0.01
7/12-7/18	29	0.298	0.150	0.297	0.110	0.309	0.090	0.255	0.11
7/19-7/25	30	0.145	0.141	0.194	0.082	0.090	0.121	0.134	0.05
7/26-8/01 3/02-8/08	31 32	0.220	0.195 0.130	0.316	0.070	0.200	0.228	0.277	0.06
8/02-8/08 8/09-8/15		0.306 0.437	0.130	0.423 0.418	0.056 0.030	0.309 0.371	0.126 0.047	0.403 0.397	0.01
Tahltan									
6/21-6/27		0.000	0.113		0.025	0.000	0.133		0.01
6/28-7/04	27	0.000	0.040		0.025	0.000	0.000		0.01
7/05-7/11 7/12 7/12	28 29	0.000	0.030		0.026 0.080	0.000	0.000		0.00
7/12-7/18 7/19-7/25		0.000 0.000	0.090 0.010		0.020	0.000	0.013 0.000		0.00
7/19-7/23 7/26-8/01	31	0.000	0.013		0.000	0.000	0.000		0.00
3/02 <b>-</b> 8/08		0.000	0.023		0.014	0.000	0.000		0.00
3/09-8/15		0.000	0.070		0.020	0.000	0.000		0.00
Stikine									
6/21-6/27		0.000	0.081		0.000	0.000	0.014		0.00
6/28-7/04		0.000	0.040		0.000	0.000	0.000		0.00
7/05 <b>-</b> 7/11		0.000	0.070		0.000	0.000	0.004		0.00
7/12 <b>-</b> 7/18		0.000	0.120		0.000	0.000	0.100		0.00
7/19-7/25 7/26 <b>-</b> 8/01		0.000	0.071		0.000 0.000	0.000	0.000 0.000		0.00
7/2 <b>0-</b> 8/01 8/02 <b>-</b> 8/08		0.000 0.000	0.092 0.070		0.000	0.000	0.000		0.00
8/02-8/08 8/09-8/15		0.000	0.100		0.000	0.000	0.059		0.00
0,000,10	~~	0.000	0.100		0.000				

Numbers of age-2.2 sockeye salmon in the escapements only to the Alaska I and Nass/Skeena systems were sufficient to construct models for this age-class, therefore the Alaska II, Tahltan, and non-Tahltan Stikine groups were not included in the age-2.2 models.

Appendix F.3. Differences between in- and postseason stock composition estimates for Alaska's Subdistrict 106-30 sockeye harvest, 1987.

Stat. Week	Group	In- Season	Post Season	Change
6/21-6/27	Alaska I	65.5	43.6	-21.91
Week 26	Alaska II	9.5	21.6	12.14
	Nass/Skeena	1.8	0.0	-1.80
	Tahltan	0.2	10.2	10.01
	Stikine	0.0	1.1	1.07
6/28-7/04	Ak. I	67.4	44.9	-22.52
Week 27	Ak. II	17.0	35.4	18.42
	Nas/Ske	2.1	10.0	7.94
	Tahltan	0.0	0.1	0.14
	Stikine	3.0	0.0	-3.00
7/05-7/11	Ak. I	74.7	67.6	-7.12
Week 28	Ak. II	10.0	11.4	1.38
	Nas/Ske	5.7	11.1	5.43
	Tahltan	0.0	0.1	0.11
	Stikine	0.0	0.3	0.25
7/12-7/18		64.5	61.5	-3.02
Week 29	Ak. II	14.4	13.0	-1.43
	Nas/Ske	12.3	10.4	-1.93
	Tahltan	0.0	0.9	0.88
	Stikine	0.5	6.7	6.22
7/19-7/25	Ak. I	75.8	41.4	-34.30
Week 30	Ak. II	5.4	42.0	36.55
	Nas/Ske	5.9	9.9	3.99
	Tahltan Stikine	0.0 5.7	0.0 0.0	0.00 -5.70
7/26-8/01	Ak. I	46.6	18.1	-28.4
Week 31	Ak. II	34.8	56.7	21.93
	Nas/Ske	12.0	17.3	5.3
	Tahltan	0.0	0.0	0.00
	Stikine	0.0	0.0	0.00
8/02-8/08	Ak. I	40.6	20.0	-20.6
Week 32	Ak. II	45.2	59.4	14.1
	Nas/Ske	4.3	10.3	5.9
	Tahltan	0.0	0.0	0.0
	Stikine	0.0	0.0	0.0
	Ak. I	59.7	37.6	-22.1
Fishery	Ak. II	22.3	40.8	18.4
Total	Nas/Ske	7.9	11.7	3.7
	Tahltan	0.0	0.4	0.4
	Stikine	1.5	1.1	-0.3

 $<sup>^{\</sup>rm a}$  For age-1.2, -1.3, and -2.3 fish only.

Appendix F.4. Log-likelihood (G) values for a comparison of weekly in-season and postseason stock composition estimates for Alaska's Sub-district 106-30 drift gill net sockeye harvest, 1987.

Date and				Stock Gro	uping			
	Estimate	Ak. I	Ak. II	Nass/Ske	Tahltan	Stikine	Total	G
6/21-6/27	' In	42	7	2	1	1	52	
Week 26	Post	37	19	1	9	2	67	
	Total	79	26	3	11	3	118	8.438
6/28-7/04	In	99	26	4	1	5	129	
Week 27	Post	66	52	16	1	1	135	
	Total	165	78	20	2	6	265	17.424
7/05-7/11	In	179	25	15	1	1	219	
Week 28	Post	162	28	27	1	2	219	
	Total	341	53	42	2	3	438	1.652
7/12-7/18	In	148	34	29	1	2	212	
Week 29	Post	177	38	31	4	20	250	
	Total	326	72	60	5	22	462	-12.792
7/19-7/25	In	178	14	15	1	14	207	
Week 30	Post	105	107	26	1	1	239	
	Total	283	120	41	2	15	446	93.983
7/26-8/01	In	75	5 <b>6</b>	20	1	1	153	
Week 31	Post	42	130	41	1	1	214	
	Total	117	187	61	2	2	367	33.225
8/02-8/08	In	83	92	10	1	1	185	
Week 32	Post	45	132	24	1	1	201	
	Total	128	224	33	2	2	386	20.958
-	In	756	283	100	0	19	1158	
Totals a	Post	5 <b>46</b>	593	170	6	16	1331	
	Total	1301	875	271	6	35	2488	159.939

<sup>&</sup>lt;sup>a</sup> Totals are for weighted weekly samples and thus are not direct sums of weekly samples.

Appendix F.5. In-season initial and adjusted stock composition estimates for sockeye salmon harvested in Alaska's Subdistrict 106-41 drift gill net fishery, 1987.

	5+ -+	Ini	tial Esti	mate	Adju	sted Esti	mate
Date	Stat. Week	1.2	1.3	2.3	1.2	1.3	2.3
Alaska I							
6/21-6/27	26	- 0.956	0.493	0.477	1.000	0.781	0.734
6/28-7/04	27	0.522	0.531	0.214	0.985	0.783	0.201
7/05-7/11	28	0.396	0.369	0.243	0.796	0.583	0.255
7/12-7/18	29	0.514	0.534	0.215	0.720	0.716	0.602
7/19-7/25	30	0.625	0.452	0.216	0.965	0.638	0.479
7/26-8/01	31	0.383	0.396	0.430	0.908	0.462	0.834
8/02-8/08	32	0.442	0.361	0.230	0.653	0.500	0.567
Alaska II							
6/21-6/27	26	0.022	0.239	0.277	0.000	0.102	0.155
6/28-7/04	27	0.217	0.198	0.429	0.000	0.121	0.475
7/05-7/11	28	0.189	0.160	0.385	0.003	0.048	0.400
7/12-7/18	29	0.167	0.228	0.544	0.040	0.160	0.328
7/19-7/25	30	0.150	0.322	0.647	0.000	0.179	0.521
7/26-8/01	31	0.255	0.380	0.370	0.000	0.420	0.166
8/02-8/08	32	0.093	0.369	0.540	0.000	0.341	0.433
Nass/Skeer	ı <b>a</b>	_					
6/21-6/27	26	0.022	0.067	0.108	0.000	0.039	0.031
6/28-7/04	27	0.174	0.125	0.143	0.015	0.096	0.136
7/05-7/11	28	0.151	0.257	0.141	0.201	0.298	0.120
7/12-7/18	29	0.167	0.140	0.101	0.121	0.124	0.070
7/19-7/25	30	0.150	0.101	0.029	0.035	0.096	0.000
7/26-8/01	31	0.085	0.139	0.040	0.092	0.118	0.000
8/02-8/08	32	0.395	0.156	0.040	0.347	0.159	0.000
Tahltan b							
6/21-6/27	26	-	0.158	0.138		0.078	0.080
6/28-7/04	27		0.099	0.089		0.000	0.029
7/05-7/11	28		0.155	0.090		0.071	0.002
7/12-7/18	29		0.041	0.013		0.000	0.000
7/19-7/25	30		0.070	0.000		0.000	0.000
7/26-8/01	31		0.037	0.030		0.000	0.000
8/02-8/08	32		0.064	0.010		0.000	0.000
Stikine							
6/21-6/27	26	0.000	0.043	0.000	0.000	0.000	0.000
6/28-7/04	27	0.087	0.047	0.125	0.000	0.000	0.159
7/05-7/11	28	0.264	0.059	0.141	0.000	0.000	0,223
7/12-7/18	29	0.152	0.057	0.127	0.119	0.000	0.000
7/19-7/25	30	0.075	0.055	0.108	0.000	0.087	0.000
7/26-8/01	31	0.277	0.048	0.130	0.000	0.000	0.000
8/02-8/08	32	0.070	0.050	0.180	0.000	0.000	0.000
0,02 0,00	32	0.070	0.030	0.100	0.000	0.000	0.000

Age-2.2 sockeye salmon were not analyzed in-season.

The number of age-1.2 fish sampled from the 1986 Tahltan escapement was insufficient to build a standard, thus the in-season models in 1987 did not include age-1.2 Tahltan fish.

Appendix F.6. Postseason initial and adjusted stock composition estimates for sockeye salmon harvested in Alaska's Subdistrict 106-41 drift gill net fishery, 1987.

Date			Initial	Estimate		Adjusted Estimate				
	Stat. Week	1.2	1.3	2.2	2.3	1.2	1.3	2.2 ª	2.	
Alaska I										
6/21-6/27	26	0.934	0.430	0.936	0.461	0.996	0.694	1.000	0.75	
6/28-7/04	27	0.787	0.464	0.796	0.428	0.975	0.684	0.855	0.65	
7/05-7/11	28	0.528	0.247	0.474	0.376	0.643	0.365	0.475	0.569	
7/12-7/18	29	0.575	0.394	0.690	0.481	0.728	0.712	0.730	0.76	
7/19-7/25	30	0.675	0.307	0.825	0.392	0.925	0.449	0.889	0.47	
7/26-8/01	31	0.575	0.251	0.519	0.370	0.726	0.370	0.529	0.47	
8/02-8/08 8/09-8/15	32 33	0.442 0.493	0.241 0.394	0.422 0.429	0.180 0.160	0.697 0.682	0.346 0.758	0.414 0.422	0.00	
	33	0.493	0,534	0.429	0.100	0.002	0.756	0.422	0.00	
Alaska II										
6/21-6/27	26	0.022	0.311		0.262	0.004	0.215		0.04	
6/28-7/04	27	0.043	0.266		0.304	0.000	0.164		0.14	
7/05-7/11	28	0.132	0.283		0.260	0.000	0.253		0.11	
7/12-7/18	29	0.258	0.321		0.316	0.142	0.171		0.11	
7/19-7/25	30	0.175	0.427		0.559	0.000	0.429		0.52	
7/26-8/01	31	0.255	0.524		0.570	0.139	0.518		0.52	
8/02-8/08	32	0.093	0.468		0.740	0.000	0.458		0.97	
8/09-8/15	33	0.145	0.276		0.770	0.000	0.096		0.98	
Nass/Skeer	na									
6/21-6/27	26	0.044	0.110	0.064	0.154	0.000	0.091	0.000	0.08	
6/28-7/04	27	0.170	0.156	0.204	0.143	0.025	0.152	0.145	0.07	
7/05-7/11	28	0.340	0.299	0.526	0.182	0.357	0.342	0.525	0.12	
7/12-7/18	29	0.167	0.140	0.310	0.127	0.130	0.117	0.270	0.05	
7/19-7/25	30	0.150	0.121	0.175	0.039	0.075	0.089	0.111	0.00	
7/26-8/01	31	0.170	0.123	0.481	0.060	0.135	0.112	0.471	0.00	
8/02-8/08	32	0.465	0.177	0.578	0.070	0.303	0.196	0.586	0.02	
8/09-8/15	33	0.362	0.165	0.571	0.060	0.318	0.146	0.578	0.01	
Tahltan		ī								
6/21-6/27	26	0.000	0.077		0.123	0.000	0.000		0.12	
6/28-7/04	27	0.000	0.078		0.125	0.000	0.000		0.12	
7/05-7/11	28	0.000	0.096		0.182	0.000	0.036		0.19	
7/12-7/18	29	0.000	0.062		0.076	0.000	0.000		0.06	
7/19-7/25	30	0.000	0.065		0.010	0.000	0.011		0.00	
7/26-8/01	31	0.000	0.059		0.000	0.000	0.000		0.00	
8/02-8/08	32	0.000	0.050		0.010	0.000	0.000		0.00	
8/09-8/15	33	0.000	0.063		0.010	0.000	0.000		0.00	
Stikine										
6/21-6/27	26	0.000	0.072		0.000	0.000	0.000		0.00	
6/28-7/04	27	0.000	0.036		0.000	0.000	0.000		0.00	
7/05-7/11	28	0.000	0.075		0.000	0.000	0.004		0.00	
7/12-7/18	29	0.000	0.083		0.000	0.000	0.000		0.00	
7/19-7/25	30	0.000	0.080		0.000	0.000	0.022		0.00	
7/26-8/01	31	0.000	0.043		0.000	0.000	0.000		0.00	
8/02-8/08	32	0.000	0.064		0.000	0.000	0.000		0.00	
8/09-8/15	33	0.000	0.102		0.000	0.000	0.000		0.00	

Numbers of age-2.2 sockeye salmon in the escapements only to the Alaska I and Nass/ Skeena systems were sufficient to construct models for this age-class, therefore the Alaska II, Tahltan, and non-Tahltan Stikine groups were not included in the age-2.2 models.

Appendix F.7. Differences between in- and postseason stock composition estimates for Alaska's Subdistrict 106-41 sockeye harvest, 1987.

Stat.		In-	Post	
week	Group	Season	Season	Change
6/21-6/27	Alaska I	71.4	65.4	-6.0
Week 26	Alaska II	9.0	15.8	6.
	Nass/Skeena	3.1	7.4	4.
	Tahltan	6.4	1.3	-5.
	Stikine	0.0	0.0	0.
5/28-7/04	Ak. I	65.5	63.4	-2.
Veek 27	Ak. II	13.5	13.1	-0.
	Nas/Ske	8.3	11.8	3.
	Tahltan	0.3	1.3	1.
	Stikine	1.7	0.0	-1.
7/05-7/11	Ak. I	50.9	38.4	-12.
Veek 28	Ak. II	8.6	19.0	10.
	Nas/Ske	24.0	28.5	4.
	Tahltan	5.0	5.0	-0.
	Stikine	2.9	0.3	-2.
7/12-7/18	Ak. I	65.8	67.7	1.
leek 29	Ak. II	15.9	15.0	-0.
	Nas/Ske	10.9	10.3	-0.
	Tahltan	0.0	0.8	0.
	Stikine	1.3	0.0	-1.
7/19-7/25	Ak. I	58.3	44.9	-13.
Week 30	Ak. II	21.2	38.5	17.
	Nas/Ske	6.8	6.6	-0.
	Tahltan Stikine	0.0 6.0	0.8 1.5	0. -4.
	SCIRINE	0.0	1.5	-4.
7/26-8/01		52.6	38.2	-14.
Week 31	Ak. II	29.7	44.2	14.
	Nas/Ske	8.1	8.1	-0.
	Tahltan	0.0	0.0	0.
	Stikine	0.0	0.0	0.
3/02-8/08		46.5	24.9	-21.
Week 32	Ak. II	29.3	48.8	19.
	Nas/Ske	11.7	13.9	2.
	Tahltan	0.0	0.0	0.
	Stikine	0.0	0.0	0.
<b>-</b> . ,	Ak. I	57.5	46.8	-10.
Fishery	Ak. II	18.1	28.9	10.
Total	Nas/Ske	11.9	13.5	1.
	Tahltan	1.4	1.5	0.
	Stikine	2.2	0.3	-1.

 $<sup>^{\</sup>mathrm{a}}$  For age-1.2, 1.3, and 2.3 fish only.

Appendix F.8. Log-likelihood (G) values for a comparison of weekly in-season and postseason stock composition estimates for Alaska's Subdistrict 106-41 drift gill net sockeye harvest, 1987.

Date		Stock Grouping						
and Week E	Istimate	Ak. I	Ak. II	Nass/Ske	Tahltan	Stikine	Total	G
6/21-6/27	In	229	30	11	21	1	291	
Week 26	Post	209	51	24	5	1	290	
	Total	438	81	35	27	2	581	19.989
6/28-7/04	In	194	41	25	2	6	262	
Week 27	Post	188	40	36	5	1	268	
	Total	382	80	61	7	7	531	-2.595
7/05-7/11	In	162	28	77	17	10	285	
Week 28	Post	123	61	91	17	2	293	
	Total	285	90	169	34	12	577	8.698
7/12-7/18	In	223	55	38	1	5	317	
Week 29	Post	230	52	36	4	1	321	
	Total	453	106	74	5	6	638	-3.590
7/19-7/25	In	200	73	24	1	21	298	
Week 30	Post	154	132	24	4	6	314	
	Total	354	206	48	5	28	612	-4.959
7/26-8/01	In	177	100	28	1	1	306	
Week 31	Post	129	149	=	1	1	306	
	Total	305	249	56	2	2	612	14.267
8/02-8/08	In	133	84	34	1	1	253	
Week 32	Post	72	139		1	1	253	
	Total	205	224	75	2	2	505	30.194
_	In	1281	403		32	50	2032	
Totals a	Post	1042	644		33	8	2028	
	Total	2324	1047	567	66	57	4060	117.443

<sup>&</sup>lt;sup>a</sup> Totals are for weighted weekly samples and thus are not direct sums of weekly samples.

Appendix F.9. In-season initial and adjusted stock composition estimates for sockeye salmon harvested in Canada's Stikine River commercial fishery, 1987.

		Init	ial Estima	ate	Adjusted Estimate			
Date	Stat. Week	1.3	2.3 b	0.	1.3	2.3 b	0.	
Tahltan								
6/28-7/04	27	0.846		1.000	0.888		1.000	
7/05-7/11	28	0.868		1.000	0.914		1.000	
7/12-7/18	29	0.691	0.690	1.000	0.704	0.795	1.000	
7/19-7/25	30	0.403	0.524	1.000	0.360	0.395	1.000	
7/26-8/01	31	0.312		1.000	0.260		1.000	
8/02-8/08	32	0.099		1.000	0.041		1.000	
non-Tahlta	ın							
6/28-7/04	27	0.154		0.000	0.112		0.000	
7/05-7/11	28	0.132		0.000	0.086		0.000	
7/12-7/18	29	0.309	0.310	0.000	0.296	0.205	0.000	
7/19-7/25	30	0.597	0.476	0.000	0.640	0.065	0.000	
7/26-8/01	31	0.688		0.000	0.740		0.000	
8/02-8/08	32	0.901		0.000	0.959		0.000	

a Age-1.2 and -2.2 sockeye were not analyzed in-season.
b Age-2.3 sockeye were analyzed only during statistical weeks 29-30.

Appendix F.10. Postseason initial and adjusted stock composition estimates for sockeye salmon caught in the Stikine River test fishery and in Canada's lower river commercial fishery, 1987.

	Ch. h		Initial	Estimate			Adjusted	Estimate	
Date	Stat. Week	1.2	1.3	2.2	2.3	1.2	1.3	2.2	2.3
Commercia	l Fishery								
Tahltan									
6/28-7/04	27	0.333	0.744	0.571	0.714	0.159	0.803	0.607	0.784
7/05-7/11		0.333	0.897	0.571	0.714	0.159	1.000	0.607	0.784
7/12-7/18		0.500	0.695	0.571	0.690	0.369	0.740	0.607	0.746
7/19-7/25		0.294	0.360	0.353	0.429	0.110	0.304	0.375	0.329
7/26-8/01		0.143	0.286	0.133	0.190	0.000	0.207	0.142	0.000
8/02-8/08		0.353	0.130	0.133	0.320	0.184	0.004	0.142	0.156
8/09-8/15		0.313	0.111	0.417	0.235	0.133	0.000	0.443	0.021
8/16-8/22		0.357	0.143	0.417	0.235	0.189	0.021	0.443	0.021
8/23-9/19		0.357	0.152	0.417	0.235	0.189	0.032	0.443	0.021
non-Tahlt	an Stikine								
6/28-7/04	27	0.667	0.256	0.429	0.286	0 041	0 107	0.303	0.014
7/05-7/11		0.667				0.841	0.197	0.393	0.216
			0.103 0.305	0.429	0.286	0.841	0.000	0.393	0.216
7/12-7/18		0.500		0.429	0.310	0.631	0.260	0.393	0.254
7/19-7/25		0.706	0.640	0.647	0.571	0.890	0.696	0.625	0.671
7/26-8/01		0.857	0.714	0.867	0.810	1.000	0.793	0.858	1.000
8/02-8/08		0.647	0.870	0.867	0.680	0.816	0.996	0.858	0.844
8/09-8/15		0.687	0.889	0.583	0.765	0.867	1.000	0.557	0.979
8/16-8/22 8/23-9/19		0.643 0.643	0.857 0.848	0.583 0.583	0.765 0.765	0.811 0.811	0.979 0.968	0.557 0.557	0.979
Test Fish	nery								
Tahltan									
6/21-7/04	26-27	0.471	0.852	0.571	0.545	0.332	0.944	0.607	0.515
7/05-7/11	28	0.471	0.774	0.571	0.545	0.332	0.842	0.607	0.515
7/12-7/18	3 29	0.471	0.619	0.571	0.625	0.332	0.641	0.607	0.642
7/19-7/25	30	0.350	0.375	0.571	0.429	0.180	0.323	0.607	0.329
7/26-8/01	31	0.261	0.209	0.333	0.250	0.068	0.106	0.354	0.045
8/02-8/08	32	0.259	0.218	0.333	0.143	0.066	0.119	0.354	0.000
8/09-8/15		0.160	0.103	0.333	0.062	0.000	0.000	0.354	0.000
8/16-9/12		0.160	0.044	0.333	0.062	0.000	0.000	0.354	0.000
non-Tahlt	an Stikine	ı							
6/21-7/04	26-27	0.529	0.148	0.429	0.455	0.668	0.056	0.393	0.485
7/05-7/11		0.529	0.226	0.429	0.455	0.668	0.158	0.393	0.485
7/12-7/18		0.529	0.226	0.429	0.435	0.668	0.158	0.393	0.358
7/19-7/25		0.650	0.625		0.571		0.559	0.393	0.336
				0.429		0.820	0.894		
		0.739	0.791	0.667	0.750	0.932		0.646 0.646	0.955
7/26-8/01		0 741	0 702						
7/26-8/01 8/02-8/08	3 32	0.741	0.782	0.667	0.857	0.934	0.881		
7/26-8/01	3 32 5 33	0.741 0.840 0.840	0.782 0.897 0.956	0.667 0.667 0.667	0.857 0.938 0.938	1.000	1.000	0.646 0.646	1.000

Appendix F.11. Differences between the in- and postseason stock composition estimates for Canada's Stikine River sockeye harvest, 1987.

				<del></del>
Stat.		In-	Post	
Week	Group	Season	Season	Change
6/28 7/04	m-11	71 0	62.7	7.2
6/28-7/04		71.0	63.7	-7.3
Week 27	non-Tahltan	11.0	17.9	6.9
7/05-7/11	Tahltan	75.8	81.7	5.9
Week 28	non-Tahltan	7.1	1.2	-5.9
7/12-7/18	Tahltan	58.9	61.0	2.1
Week 29	non-Tahltan	28.5	26.3	-2.2
7/19-7/25	Tahltan	24.8	20.8	-4.0
Week 30	non-Tahltan	55.0	58.9	3.9
7/26-8/01	Tahltan	6.7	10.7	4.0
Week 31		66.9	63.7	-3.2
8/02-8/08	Mahl+an	0.0	1.0	1.0
Week 32	· · · · · -	78.0	76.0	-2.0
Fishery	Tahltan	21.4	21.2	-0.2
Totals	non-Tahltan	58.5	58.3	-0.2

a For age-1.3 and -0. fish in weeks 27 and 28 and age-1.3, -2.3, and -0. fish in weeks 29-32.

Appendix F.12. Log-likelihood (G) values for a comparison of weekly in- and postseason stock composition estimates for Canada's Stikine River commercial sockeye harvest, 1987.

Data		Stock G	rouping		
Date and Week	Estimate	Tahltan	non- Tahltan	Total	G
6/28-7/04	In	28	5	33	
Week 27	Post	26	7	33	
	Total	5 <b>4</b>	12	65	0.335
7/05-7/11	In	53	4	57	
Week 28	Post	56	1	57	
	Total	109	6	114	1.839
7/12-7/18	In	197	94	291	
Week 29	Post	203	88	291	
	Total	399	183	582	0.299
7/19-7/25	In	81	181	263	
Week 30	Post	69	193	262	
	Total	150	375	525	1.324
7/26-8/01	In	10	91	101	
Week 31	Post	14	88	102	
	Total	24	179	203	0.884
8/02-8/08	In	1	147	147	
Week 32	Post	1	144	145	
	Total	2	291	293	0.420
	In	235	641	877	
Totals a	Post	232	640	872	
	Total	467	1281	1749	0.010

Totals are for weighted weekly samples and thus are not the direct sums of weekly samples.

Because the Alaska Department of Fish and Game receives federal funding, all of its public programs and activities are operated free from discrimination on the basis of race, religion, color, national origin, age, sex, or handicap. Any person who believes he or she has been discriminated against should write to:

O.E.O. U.S. Department of the Interior Washington, D.C. 20240